

## **ADDENDUM NO. 2**

The Construction of  
City of Bismarck Solid Waste Management Facility  
Cell 1 Construction – LF 2021-001  
Bismarck, North Dakota

**Date of Issue:** Thursday April 22, 2021

**Date of Bid Opening:** Wednesday April 28, 2021 @ 4:00 p.m.

### **NOTICE TO ALL PLANHOLDERS:**

Please insert this Addendum into your copy of the project Contract Documents.

The following changes and/or additions to the Contract Documents for the project are issued by the Engineer and shall have the same force and effect as though part of the original issue.

A copy of the sign-in sheet from the pre-bid meeting as attached herein.

### **REVISIONS TO THE CONTRACT DOCUMENTS:**

#### **1. INSTRUCTIONS TO BIDDERS:** Add the following after the last paragraph on Page 4:

As a part of the solicitation response the CONTRACTOR shall provide, as an attachment to the bid, a cost summary breakdown of the material and labor components of Bid Items relating to the geosynthetic liner materials. This cost summary breakdown applies to the following Bid Items:

- Bid Item 29 (Special Provision 11) HDPE Geomembrane Liner (60 mil)
- Bid Item 30 (Special Provision 12) Geocomposite Drainage Layer
- Bid Item 51 (Special Provision 35) Geotextile Fabric

The response should also include a summary of the anticipated number of mobilization(s) to install each of the proposed materials.

#### **2. APPROXIMATE QUANTITIES and PROPOSAL BID FORM:** The following revisions have been made to the APPROXIMATE QUANTITIES and BID PROPOSAL FORM:

- **Remove** item 1207-2.3 (Geotextile Fabric Reinforcement) and **Replace** with Special Provision 35 – Geotextile Fabric. This revision was necessitated based on material specification. The material quantity has been reduced to minimize waste based on available roll widths to an amount of 3,898 SQUARE YARDS. See plan revisions of Detail B on Sheet D-2.
- **Revise** item 801-4.60 (Pipe Bedding Material) to an amount of 1,770 TON.
- **Add** item 801-4.1 (6" PVC Sanitary Sewer (SS) Pipe) in the amount of 48 LINEAR FEET
- **Revise** item 901-2.5 (6" Gate Valve w/box) to an amount of 2 by EACH
- **Add** item 901-2.5 (8" Gate Valve w/Box) in the amount of 1 by EACH

**Replace** the Approximate Quantities Page in the Instructions to Bidders section and the Proposal Bid Form with the attached revised APPROXIMATE QUANTITIES (rev1) page and the attached revised PROPOSAL BID FORM (rev 1).

#### **3. ATTACHMENT NO. 1: Update** Table 4-1 under the "Calcium Carbonate Content (ASTM D304297, pH = 4.0) by removing the following text: "Acceptable Criteria $\leq$ 0.5% content by weight" from both the Sand Drainage Layer and Leachate Collection Gravel columns.

Calcium Carbonate testing will be required as a component of the project. Source testing results will not be considered a condition of material acceptance.

4. ATTACHMENT NO. 2: Add ATTACHMENT 2 – Factual Report – Bismarck Landfill Sand Exploration for Cell 1 (attached herein) after ATTACHMENT 1.
5. ATTACHMENT NO. 3: Add ATTACHMENT 3 – Compliance Testing results from previous (excavation phase) of project (attached herein) after ATTACHMENT 2.

#### **REVISIONS TO THE SPECIFICATIONS:**

1. Special Provisions - Contractors Special Requirements: **Add** the following after paragraph eight (8):

The Engineer will provide electronic surfaces files of the existing and proposed grading available to the CONTRACTOR upon request. To obtain the surface files the CONTRACTOR must submit a completed version of the attached “DISCLAIMER FOR THE USE OF ELECTRONIC MEDIA” form to Dennis McAlpine at [dmcalpine@houstoneng.com](mailto:dmcalpine@houstoneng.com)

The provided files were generated and compatible with AutoCAD version 2020. Houston Engineering, Inc will not manipulate the files in any way to provide compatibility to other software platforms and/or earlier version of AutoCAD.

As a result of the current supply chain uncertainties associated with the production and availability of resin-based products the OWNER will accommodate for material price adjustments applied to resin-based products limited to HDPE Geomembrane Liner, Geocomposite Drainage Layer and Geotextile Fabric.

The CONTRACTOR or OWNER may request a price adjustment for these materials if the material price **increases or decreases** by 10% from the time of bidding to product order.

The request, along with supporting documentation and/or invoices, shall be provided within 21 days of product order. Payment for materials will be based on the unit prices bid for the project. The bid prices for these materials will be **increased or decreased by the amount above or below the 10% increase or decrease** based on the differing cost of material pricing.

2. SPECIAL PROVISION NO. 7 – Buffer Layer (CV) (P): **Remove** the second and third paragraphs under PART 3 – EXECUTION / TESTING and replace with the following:

“Construction Quality Control (CQC) – CONTRACTOR provided:

Buffer Layer materials will be tested via a Construction Quality Control (CQC) process by the Contractor at their source (source testing) for their respective required parameters using the testing procedures as defined in the CQAP provided in Attachment 1. The Buffer Layer materials shall be tested at ½ the interval as defined for the Re-Compacted Clay Barrier Layer. The Contractor will submit the required testing data to the Engineer for approval prior to acceptance of Buffer Layer material for use in the project.

Construction Quality Assurance (CQA) – OWNER provided:

The Engineer will conduct Construction Quality Assurance (CQA) testing during construction of Buffer Layer material for required parameters using the testing procedures as defined in the CQAP provided in Attachment 1. The Buffer Layer materials shall be tested at ½ the interval as defined for the Re-Compacted Clay Barrier Layer. A soils testing lab will be contracted to the Engineer or Owner to conduct the required assurance testing. The CQA program consists of:”

3. SPECIAL PROVISION NO. 8 – Re-Compacted Clay Barrier Layer (CV) (P): **Revise** the second sentence of paragraph 2 under PART 3 – EXECUTION / PLACEMENT as follows:

“Re-Compacted Soil Barrier Layer shall be placed at 2% to 5% wet of optimum moisture content.”

4. SPECIAL PROVISION NO. 15 – Leachate Riser Structure: **Add** the following after the last bullet under the MEASUREMENT AND PAYMENT section:

- “Furnish and install DIP stand-pipe including hardware.”

5. SPECIAL PROVISION NO. 35 – Geotextile Fabric: **Add** special provision (attached herein) following Special Provision 34 – Instruments.

#### **REVISIONS TO THE PLANS:**

1. Plan Sheet C-1: **Revise** the call-out denoting the “PREFERRED LOCATION OF REMOVALS/PLACEMENT” to display as “SECONDARY LOCATION OF REMOVALS/PLACEMENT”. **Update** sheet to include the following note: “NOTE 1. THE OWNER HAS PROVIDED A STOCKPILE OF TOPSOIL MATERIALS FOR USE BY THE CONTRACTOR. THE TOPSOIL MATERIALS ARE STOCKPLIED IN FUTURE CELLS 3-4.”
2. Plan Sheet PP-11: **Revise** call-out on sanitary sewer profile removing reference to 6” diameter piping. **Replace** call-out text as follows: “282’-0” 8” SDR 21 @ 0.6%”
3. Plan Sheet D-2: **Revise** call-out and dimensioning on Detail B denoting width of “CUSHION GEOTEXTILE CUSHION” from 16.0 feet to 15.0 feet.

All other requirements and stipulations of the plans and specifications shall remain in effect.  
The receipt of this addendum shall be acknowledged in the Bidder's Proposal.

HOUSTON ENGINEERING, INC.

***This document was originally issued and sealed by Dennis McAlpine, PE, North Dakota Registration Number PE-9886, on April 22, 2021, and the original documents are stored at Houston Engineering, Inc., 3712 Lockport Street, Bismarck, ND.***

By: \_\_\_\_\_  
Dennis McAlpine, P.E.  
ND Reg. No. 9886

PRE-BID SIGN-IN SHEET

City of Bismarck Solid Waste Management Facility  
 Cell 1 Construction  
 City of Bismarck, ND  
 Wednesday, April 14, 2021

NAME	COMPANY/ORGANIZATION	PHONE		EMAIL
		Office	Cell	
Ryan Holte	RS Zaveroni & Sons	(218) 773-0586		rholt@rjzaveroni.com
		Cell	(218) 230-1189	
Jeremy Rish	Running Horse LLC	Office		jeremy@runninghorsetrucking.com
		Cell	701-421-4479	
Tell Fredericks	Running Horse LLC	Office		fredericks@rm@live.com
		Cell	701-870-0128	
Richard Vorpak	MK WEEDEN Construction, INC.	Office		rvorpak@mkweeden.com
		Cell	847-867-7062	
JAY HOLLEN	STRATA Corporation	Office		JAY@HOLLEN.COM
		Cell	701-500-4237	STRATACORPORATION.COM
NATHAN KEMIP	MARTIN	Office		nkemip@martinind.com
		Cell	915-497-8328	
JOE KESSEL	BARAKO Bros Inc	Office	701-483-5868	joe@barakobros.com
		Cell	701-290-8375	
Cody Idso	BARAKO Bros Inc	Office	701-483-5868	Codyidso@barakobros.com
		Cell	701-430-0719	
		Office		
		Cell		

PRE-BID SIGN-IN SHEET

City of Bismarck Solid Waste Management Facility  
 Cell 1 Construction  
 City of Bismarck, ND  
 Wednesday, April 14, 2021

NAME	COMPANY/ORGANIZATION	PHONE		EMAIL
		Office	Cell	
Cody Frederick	Running Horse LLC	Office	870-0129	Cody@RunningHorseTrucking.com
		Cell	320-393-4160	
Jocelyn Henderson	Burski EA	Office		
		Cell		
		Office		
		Cell		
		Office		
		Cell		
		Office		
		Cell		
		Office		
		Cell		
		Office		
		Cell		
		Office		
		Cell		

PRE-BID SIGN-IN SHEET

City of Bismarck Solid Waste Management Facility  
 Cell 1 Construction  
 City of Bismarck, ND  
 Wednesday, April 14, 2021

NAME	COMPANY/ORGANIZATION	PHONE		EMAIL
		Office	Cell	
Craig Griesbach	Jensen Brothers		701-561-1805	Craig@jensenbrothers Construction.com
James Smell	Mini Excavation	Office		jim@miniexcavation.com
		Cell	701-319-6319	
Garrett Bietz	Dan Hart Patrol Service	Office		bietzga@danhartpatrol.com
		Cell	307-622-0421	
		Office		
		Cell		
		Office		
		Cell		
		Office		
		Cell		
		Office		
		Cell		
		Office		
		Cell		
		Office		
		Cell		

PRE-BID SIGN-IN SHEET

City of Bismarck Solid Waste Management Facility  
 Cell 1 Construction  
 City of Bismarck, ND  
 Wednesday, April 14, 2021

NAME	COMPANY/ORGANIZATION	PHONE		EMAIL
		Office	Cell	
JASON RODO	EDLING ELECTRIC	701-255-2831	701-426-6616	jasonrod@edlingelectric.com
Matt Watson	Steeles Electric	701-223-5440	701-516-2809	drew@steeleselectric.com
JOHN HONSKI	John Refrig & Electric	701-845-5712	701-490-5713	jill_lowski@hotmail.com
Derek Damm	NIC	701-223-6695	701-239-732	ddamm@nicnd.com
Chris Roen	NIC	701-223-6695	701-319-7321	croene@nicnd.com
John Pettig	NIC	701-319-2756		—

## CITY OF BISMARCK SOLID WASTE UTILITY PROJECT: LF 2021-001

## APPROXIMATE QUANTITIES

## CITY OF BISMARCK ENGINEERING DEPARTMENT

## CONTRACTORS PROPOSAL

## City of Bismarck Solid Waste Facility Project

## LF 2021-001

## (rev 1)

Bid Item No.	Tech Spec Ref#	Item Description	Unit	Quantity
1	201-2.1	Miscellaneous Removals	LS	1
2	204-3.1	Subgrade Preparation For Gravel Surface Course	SY	713
3	205-4.1	Silt Fence	LF	500
4	205-4.9	12-inch fiber rolls	LF	1,282
5	302-4.2	Class 13 Aggregate Surface	TON	998
6	801-4.60	Pipe Bedding Material	TON	1,770
7	801-4.1	6 " PVC Sanitary Sewer (SS) Pipe	LF	48
8	801-4.1	8 " PVC Sanitary Sewer (SS) Pipe	LF	286
9	802-2.19	RIPRAP Type M	TON	20
10	802-4.5	24" RCP Culvert	LF	48
11	802-4.5	12" RCP Culvert	LF	67
12	901-2.5	6" Gate valve w/box	EA	2
13	901-2.5	8" Gate valve w/box	EA	1
14	901-2.19	Insulation Boards	SY	133
15	1201-4.1	Topsoiling and Topsoil Replacement over earthen stockpiles	CY	2,315
16	1202-4.4	Class IV Seeding	SY	19,004
17	1204-4.1	Mulching	SY	19,004
18	1205-4.1	Concrete MH	EA	1
19	SP1	Mobilization and Demobilization	LS	1
20	SP2	Groundwater/Stormwater Control & Removal	MGAL	10,000
21	SP3	Watering	MGAL	100
22	SP4	Test Pit Excavation	HR	40
23	SP5	Common Excavation (CV) (P)	CY	103,952
24	SP6	Subgrade Correction (CV)	CY	2,500
25	SP7	Buffer Layer (CV) (P)	CY	16,009
26	SP8	Re-Compacted Soil Barrier Layer (CV) (P)	CY	36,617
27	SP9	Sand Drainage Layer (In-Place) (P)	CY	18,308
28	SP10	Phase Separation and Temporary Drainage Berms (CV)	CY	4,063
29	SP11	HDPE Geomembrane Liner (60 mil.)	SY	53,943
30	SP12	Geocomposite Drainage Layer	SY	25,183
31	SP13	Groundwater Underdrain (Perforated) Piping	LF	1,715
32	SP13	Groundwater Underdrain (Solid) Piping	LF	132
33	SP13	Groundwater Underdrain Discharge Piping	LF	364
34	SP14	Groundwater Underdrain - Coarse Aggregate	TON	700
35	SP15	Leachate Riser Structure	LS	1



36	SP16	Leachate Collection Trench (Perforated) Piping	LF	923
37	SP16	Leachate Collection Sideslope Cleanout (Solid) Piping	LF	1,108
38	SP16	Leachate Sump Riser (Perforated) Piping	LF	30
39	SP16	Leachate Sump Sideslope Riser (Solid) Piping	LF	470
40	SP17	Leachate Collection Trench - Drainage Aggregate	TON	557
41	SP17	Leachate Collection Trench - Coarse Filter Aggregate	TON	882
42	SP18	Bollards	EA	6
43	SP19	Rock Ditch Check	CY	85
44	SP20	Future Gas Well Drainage Enhancement	CY	375
45	SP21	Wood Chip Placement (LV)	CY	8,060
46	SP22, SP32, SP33, SP34	Leachate Collection/Underdrain Pumps & Ancillary Equipment	LS	1
47	SP26, SP27, SP28, SP31	Ancillary Equipment - Wiring Devices, Panelboards, Transformers, Unit Heaters	LS	1
48	SP23, SP24, SP25, SP29, SP 30	Electrical/Labor - Conduit & Conductors and General	LS	1
49	SP25	Electrical - Street Lighting	LS	1
50	SP23	Electrical - Capitol Electric Distribution	LS	1
51	SP35	Geotextile Fabric	SY	3,898

CITY OF BISMARCK ENGINEERING DEPARTMENT  
 CONTRACTORS PROPOSAL  
 City of Bismarck Solid Waste Facility Project  
**LF 2021-001**  
**(rev 1)**

Bid Item No.	Tech Spec Ref#	Item Description	Unit	Quantity	Unit Price	Extension
1	201-2.1	Miscellaneous Removals	LS	1		
2	204-3.1	Subgrade Preparation For Gravel Surface Course	SY	713		
3	205-4.1	Silt Fence	LF	500		
4	205-4.9	12-inch fiber rolls	LF	1,282		
5	302-4.2	Class 13 Aggregate Surface	TON	998		
6	801-4.60	Pipe Bedding Material	TON	1,770		
7	801-4.1	6 " PVC Sanitary Sewer (SS) Pipe	LF	48		
8	801-4.1	8 " PVC Sanitary Sewer (SS) Pipe	LF	286		
9	802-2.19	RIPRAP Type M	TON	20		
10	802-4.5	24" RCP Culvert	LF	48		
11	802-4.5	12" RCP Culvert	LF	67		
12	901-2.5	6" Gate valve w/box	EA	2		
13	901-2.5	8" Gate valve w/box	EA	1		
14	901-2.19	Insulation Boards	SY	133		
15	1201-4.1	Topsoiling and Topsoil Replacement over earthen stockpiles	CY	2,315		
16	1202-4.4	Class IV Seeding	SY	19,004		
17	1204-4.1	Mulching	SY	19,004		
18	1205-4.1	Concrete MH	EA	1		
19	SP1	Mobilization and Demobilization	LS	1		
20	SP2	Groundwater/Stormwater Control & Removal	MGAL	10,000		
21	SP3	Watering	MGAL	100		
22	SP4	Test Pit Excavation	HR	40		
23	SP5	Common Excavation (CV) (P)	CY	103,952		
24	SP6	Subgrade Correction (CV)	CY	2,500		
25	SP7	Buffer Layer (CV) (P)	CY	16,009		
26	SP8	Re-Compacted Soil Barrier Layer (CV) (P)	CY	36,617		
27	SP9	Sand Drainage Layer (In-Place) (P)	CY	18,308		
28	SP10	Phase Separation and Temporary Drainage Berms (CV)	CY	4,063		
29	SP11	HDPE Geomembrane Liner (60 mil.)	SY	53,943		
30	SP12	Geocomposite Drainage Layer	SY	25,183		

31	SP13	Groundwater Underdrain (Perforated) Piping	LF	1,715		
32	SP13	Groundwater Underdrain (Solid) Piping	LF	132		
33	SP13	Groundwater Underdrain Discharge Piping	LF	364		
34	SP14	Groundwater Underdrain - Coarse Aggregate	TON	700		
35	SP15	Leachate Riser Structure	LS	1		
36	SP16	Leachate Collection Trench (Perforated) Piping	LF	923		
37	SP16	Leachate Collection Sideslope Cleanout (Solid) Piping	LF	1,108		
38	SP16	Leachate Sump Riser (Perforated) Piping	LF	30		
39	SP16	Leachate Sump Sideslope Riser (Solid) Piping	LF	470		
40	SP17	Leachate Collection Trench - Drainage Aggregate	TON	557		
41	SP17	Leachate Collection Trench - Coarse Filter Aggregate	TON	882		
42	SP18	Bollards	EA	6		
43	SP19	Rock Ditch Check	CY	85		
44	SP20	Future Gas Well Drainage Enhancement	CY	375		
45	SP21	Wood Chip Placement (LV)	CY	8,060		
46	SP22, SP32, SP33, SP34	Leachate Collection/Underdrain Pumps & Ancillary Equipment	LS	1		
47	SP26, SP27, SP28, SP31	Ancillary Equipment - Wiring Devices, Panelboards, Transformers, Unit Heaters	LS	1		
48	SP23, SP24, SP25, SP29, SP 30	Electrical/Labor - Conduit & Conductors and General	LS	1		
49	SP25	Electrical - Street Lighting	LS	1		
50	SP23	Electrical - Capitol Electric Distribution	LS	1		
51	SP35	Geotextile Fabric	SY	3,898		
Project LF 2021-001 Total Bid Amount						

**ATTACHMENT  
NO. 2  
FACTUAL REPORT – BISMARCK  
LANDFILL SAND EXPLORATION  
FOR CELL 1**



## **Factual Report**

Bismarck Landfill Sand Exploration for Cell 1  
2111 N 52nd Street  
Bismarck, North Dakota

*Prepared for*

**Houston Engineering, Inc.**

March 11, 2019

Project B1900033

Braun Intertec Corporation

March 11, 2019

Project B1900033

Mr. Sherwin Wanner  
Houston Engineering, Inc.  
1401 21st Avenue North  
Fargo, ND 58102

Re: Factual Report  
Bismarck Landfill Sand Exploration for Cell 1  
2111 N 52nd Street  
Bismarck, North Dakota

Dear Mr. Wanner:

We are pleased to present this Factual Report for the exploration of the sand layer in the area of the proposed Cell 1 of the Bismarck Landfill. The new cell will be located south of the existing landfill.

Thank you for making Braun Intertec your geotechnical consultant for this project. If you have questions about this report, or if there are other services that we can provide in support of our work to date, please contact Emily Erickson at [EErickson@braunintertec.com](mailto:EErickson@braunintertec.com).

Sincerely,

BRAUN INTERTEC CORPORATION



Emily J. Erickson, EIT  
Staff Engineer



Charles W. (Wes) Dickhut, PE  
Principal/Principal Engineer

## Table of Contents

Description	Page
A. Introduction.....	1
A.1. Project Description.....	1
A.2. Site Conditions and History .....	2
A.3. Purpose.....	2
A.4. Background Information and Reference Documents.....	2
A.5. Scope of Services.....	3
B. Results .....	3
B.1. Geologic Overview .....	3
B.2. Boring Results.....	4
B.3. Groundwater .....	5
B.4. Boring Backfill.....	6
B.5. Laboratory Test Results.....	6
B.5.a. Moisture Contents .....	6
B.5.b. Atterberg Limit Tests.....	6
B.5.c. Percent Passing the #200 Sieve Test .....	7
B.5.d. Sieve Analysis with #200 Wash .....	7
C. Procedures.....	7
C.1. Penetration Test Borings.....	7
C.2. Exploration Logs .....	8
C.2.a. Log of Boring Sheets.....	8
C.2.b. Geologic Origins .....	8
C.3. Material Classification and Testing .....	8
C.3.a. Visual and Manual Classification.....	8
C.3.b. Laboratory Testing .....	8
C.4. Groundwater Measurements.....	9
D. Qualifications.....	9
D.1. Variations in Subsurface Conditions.....	9
D.1.a. Material Strata .....	9
D.1.b. Groundwater Levels .....	9
D.2. Continuity of Professional Responsibility.....	10
D.2.a. Plan Review .....	10
D.2.b. Construction Observations and Testing .....	10
D.3. Use of Report.....	10
D.4. Standard of Care.....	10

### Appendix

Soil Boring Location Sketch

Fence Diagram

Log of Boring Sheets ST-01 to ST-06

Descriptive Terminology of Soil

Descriptive Terminology of Rock

Grain Size Accumulation Graph

## A. Introduction

### A.1. Project Description

This Factual Report addresses the subsurface conditions encountered at Cell 1 at the landfill, located in Bismarck, North Dakota. The project will include the excavation of the area with the addition of an artificial liner prior to use as a landfill. The primary concern for these explorations was the extent of a permeable sand layer expected, and groundwater conditions that should be expected during excavation. Table 1 provides project details.

**Table 1. Project Description**

Aspect	Description
Anticipated top of landfill (feet)	1777 to 1780
Anticipated liner elevation (feet)	1721 to 1713

The figure below shows an illustration of the proposed site layout.

**Figure 1. Site Layout**




Figure provided by Houston Engineering dated October 3, 2018.



## **A.2. Site Conditions and History**

Currently, the site exists as an open field with a ground level between elevations 1,771 and 1,790 feet. Generally, the site is downward sloping from northeast to southwest.

## **A.3. Purpose**

The purpose of our geotechnical evaluation was to characterize subsurface geologic conditions at selected exploration locations.

## **A.4. Background Information and Reference Documents**

We reviewed the following information:

- *Expansion Area Cell 1 – Cell 1 Plan View*, prepared by Houston Engineering and dated October 3, 2018.
- *Expansion Area Cell 1 – Cell 1 Section B*, prepared by Houston Engineering and dated October 3, 2018.
- Communications with Sherwin Wanner of Houston Engineering regarding scope of work.
- *Web Soil Survey*, <http://websoilsurvey.nrcs.usda.gov/>. United States Department of Agriculture (USDA) and Natural Resources Conservation Service (NRCS).
- *Land Form and Geologic Map of Burleigh County, North Dakota*, prepared by the North Dakota Geological Survey, Bulletin 42, Plate1, not dated, used to evaluate the surficial geology on the project site.

We have described our understanding of the proposed construction and site to the extent others reported it to us. Depending on the extent of available information, we may have made assumptions based on our experience with similar projects. If we have not correctly recorded or interpreted the project details, the project team should notify us. New or changed information could require additional evaluation, analyses and/or recommendations.

## **A.5. Scope of Services**

We performed our scope of services for the project in accordance with our Proposal QTB086174 to Houston Engineering, dated November 2, 2018, and authorized on January 2, 2019. The following list describes the geotechnical tasks completed in accordance with our authorized scope of services.

- Reviewing the background information and reference documents previously cited.
- Staking and clearing the exploration location of underground utilities. Houston Engineering selected and staked the exploration locations. Houston Engineering also provided boring location elevations for our use. The Soil Boring Location Sketch included in the Appendix shows the approximate locations of the borings.
- Performing 6 standard penetration test (SPT) borings, denoted as ST-01 to ST-06, to nominal depths of 51 feet below grade across the site.
- Performing laboratory testing on select samples to aid in soil classification and engineering analysis.
- Discussion involving extent and composition of sand layer in the area of the proposed cell.

At your request, we converted Boring ST-04 to a temporary piezometer and performed a grain-size distribution test on a bulk sample of the sand obtained during drilling.

Our scope of services did not include environmental services or testing, and we did not train the personnel performing this evaluation to provide environmental services or testing. We can provide these services or testing at your request.

## **B. Results**

### **B.1. Geologic Overview**

In review of the Geologic Map referenced previously, the site appears to lie in an area generally underlain with glacial deposits. The glacial deposits consist of glacial outwash composed of sand. Underlying these glacial deposits is the Tertiary-aged Cannonball Formation which consists of

decomposed sandstone, siltstone and claystone bedrock. The surficial soils were formed from weathering of the glacial deposits.

We based the geologic origins used in this report on the soil types, and laboratory testing, and available common knowledge of the geological history of the site. Because of the complex depositional history, geologic origins can be difficult to ascertain. We did not perform a detailed investigation of the geologic history for the site.

## B.2. Boring Results

Table 2 provides a summary of the soil boring results, in the general order we encountered the strata. Please refer to the Log of Boring sheets in the Appendix for additional details. The Descriptive Terminology sheets in the Appendix include definitions of abbreviations used in Table 2.

**Table 2. Subsurface Profile Summary\***

Strata	Soil Type - ASTM Classification	Range of Penetration Resistances	Commentary and Details
Topsoil	SC	N/A	<ul style="list-style-type: none"><li>▪ Dark Brown with trace roots.</li><li>▪ Thickness at boring locations generally ½ foot.</li><li>▪ Frozen, but moist when thawed.</li></ul>
Glacial deposits	SM	12 to 32 BPF	<ul style="list-style-type: none"><li>▪ Brown.</li><li>▪ Trace roots and iron staining.</li><li>▪ Variable amounts of gravel present.</li><li>▪ Dry.</li></ul>
Cannonball Formation – Bedrock	Claystone, Sandstone	14 to 88 BPF	<ul style="list-style-type: none"><li>▪ Top of bedrock varied from elevation 1767.7 (ST-03) to 1790.3 (ST-04).</li><li>▪ Decomposed claystone texturally classified as Fat Clay (CH) with interbedded siltstone.</li><li>▪ Decomposed sandstone texturally classified as Poorly Graded Sand with Silt (SP-SM) and Silty Sand (SM).</li></ul>

\*Abbreviations defined in the attached Descriptive Terminology sheets.

Table 3 shows top and bottom elevation of sandstone layer encountered in our borings.

**Table 3. Sandstone Layer Elevations**

Aspect	Description
Approximate elevation top of sand layer (feet)	1765 to 1752
Approximate elevation bottom of sand layer (feet)	1744 to 1732

### B.3. Groundwater

Table 4 summarizes the depths where we observed groundwater; the attached Log of Boring sheets in the Appendix also include this information and additional details.

**Table 4. Groundwater Summary**

Location	Surface Elevation	Measured Depth to Groundwater (ft)	Corresponding Groundwater Elevation (ft)
ST-01	1771.6	29.5	1742 1/2
ST-02	1781.1	34.5	1747
ST-03	1773.7	27	1747
ST-04	1790.7	39.5	1751 1/2
ST-05	1774.2	27	1747 ½
ST-06	1781.4	32	1749 ½

Note: groundwater observations were rounded up to the nearest ½ foot.

A piezometer was installed in Boring ST-04 by inserting a 1-inch-diameter PVC pipe to the bottom of the borings. Screen with an opening of 0.010 inches was inserted between elevations of 1750 and 1740 feet. Filter sand was inserted from the bottom of the boring to an elevation of 1735 feet. A 2-ft-thick layer of bentonite chips was inserted on top of the sand, and then the borehole was backfilled with auger cuttings. On February 25, the water level was measured to be 1753 feet. The soil borings indicate a layered soil profile that is conducive for encountering perched water conditions in the sandstone. Project planning should expect groundwater will fluctuate in relation to seasonal and annual fluctuations.

#### **B.4. Boring Backfill**

The borings were backfilled with bentonite chips from the bottom of the boring to 5 feet above the sand layer. The remainder of each borehole was backfilled with auger cuttings.

#### **B.5. Laboratory Test Results**

We performed 16 moisture contents (per ASTM D2216), 2 Atterberg limits (per ASTM D4318), and 3 percent passing the No. 200 sieve tests (per ASTM D1140) and 1 Sieve Analysis with 200 wash (per ASTM C 136 and C 117) on representative samples obtained from the borings.

##### **B.5.a. Moisture Contents**

We performed moisture content (MC) tests (per ASTM D2216) on selected samples to aid in our classifications and estimations of the material's engineering properties. Table 5 below presents the results of our moisture content tests.

**Table 5. Moisture Content Results.**

<b>Material Type</b>	<b>Moisture Content Range (%)</b>	<b>Above/Below Estimated Optimum Moisture</b>
Fat Clay (CH)	18 to 32	At or Above
Sandstone (SP-SM)	1 to 25	Below to Above
Claystone (CH)	22 to 26	At or Above

##### **B.5.b. Atterberg Limit Tests**

We performed Atterberg Limits tests (per ASTM D4318) on select samples. The results of these tests were used to estimate the plasticity of the clay and are shown on Table 6 below.

**Table 6. Atterberg Limit Results**

Sample Location	Liquid Limit	Plastic Limit	Plasticity Index	Soil Classification
ST-04, 5 feet	63	21	42	Fat Clay (CH)
ST-04, 15 feet	84	26	58	Fat Clay (CH)

**B.5.c. Percent Passing the #200 Sieve Test**

We performed tests to evaluate the percent of particles passing the #200 sieve (P200, per ASTM D1140) to confirm our visual classification. The result of these tests indicated that the sandstone soils tested had silt contents of 11 to 14 percent. The Log of Boring sheets list the results of the P200 test in the “Tests or Notes” column.

**B.5.d. Sieve Analysis with #200 Wash**

We performed a sieve analysis with a #200 wash (per ASTM C 136 and C117) to determine grain size distribution of a representative sample of the granular material. The result of this test can be found on the Grain Size Distribution Curve in the attachments. We performed this test from collecting a bag sample of boring ST-04 from 30 to 40 feet, which corresponds to the sandstone layer we investigated. The resulting sample was composed of 34 percent fine sand, and less than 1 percent silt-sized material.

**C. Procedures**

**C.1. Penetration Test Borings**

We drilled the penetration test borings with a truck-mounted core and auger drill equipped with hollow-stem auger. We performed the borings in general accordance with ASTM D6151 taking penetration test samples at 2 1/2- or 5-foot intervals in general accordance to ASTM D1586. The boring logs show the actual sample intervals and corresponding depths. We also collected bulk samples of auger cuttings at selected locations for laboratory testing.

## **C.2. Exploration Logs**

### **C.2.a. Log of Boring Sheets**

The Appendix includes Log of Boring sheets for our penetration test borings. The logs identify and describe the penetrated geologic materials, and present the results of penetration resistance and other tests performed. The logs also present the results of laboratory tests performed on penetration test samples, and groundwater measurements. The Appendix also includes a Fence Diagram intended to provide a summarized cross-sectional view of the soil profile across the site.

We inferred strata boundaries from changes in the penetration test samples and the auger cuttings. Because we did not perform continuous sampling, the strata boundary depths are only approximate. The boundary depths likely vary away from the boring locations, and the boundaries themselves may occur as gradual rather than abrupt transitions.

### **C.2.b. Geologic Origins**

We assigned geologic origins to the materials shown on the logs and referenced within this report, based on: (1) a review of the background information and reference documents cited above, (2) visual classification of the various geologic material samples retrieved during the course of our subsurface exploration, (3) penetration resistance and other in-situ testing performed for the project, (4) laboratory test results, and (5) available common knowledge of the geologic processes and environments that have impacted the site and surrounding area in the past.

## **C.3. Material Classification and Testing**

### **C.3.a. Visual and Manual Classification**

We visually and manually classified the geologic materials encountered based on ASTM D2488. When we performed laboratory classification tests, we used the results to classify the geologic materials in accordance with ASTM D2487. The Appendix includes a chart explaining the classification system we used.

### **C.3.b. Laboratory Testing**

The exploration logs in the Appendix note most of the results of the laboratory tests performed on geologic material samples. The remaining laboratory test results follow the exploration logs. We performed the tests in general accordance with ASTM procedures.

## **C.4. Groundwater Measurements**

The drillers checked for groundwater while advancing the penetration test borings, and again after auger withdrawal. We then filled the boreholes or allowed them to remain open for an extended period of observation, as noted on the boring logs. One boring was converted to a temporary piezometer.

## **D. Qualifications**

### **D.1. Variations in Subsurface Conditions**

#### **D.1.a. Material Strata**

We developed our evaluation, analyses and recommendations from a limited amount of site and subsurface information. It is not standard engineering practice to retrieve material samples from exploration locations continuously with depth. Therefore, we must infer strata boundaries and thicknesses to some extent. Strata boundaries may also be gradual transitions, and project planning should expect the strata to vary in depth, elevation and thickness, away from the exploration locations.

Variations in subsurface conditions present between exploration locations may not be revealed until performing additional exploration work, or starting construction. If future activity for this project reveals any such variations, you should notify us so that we may reevaluate our recommendations. Such variations could increase construction costs, and we recommend including a contingency to accommodate them.

#### **D.1.b. Groundwater Levels**

We made groundwater measurements under the conditions reported herein and shown on the exploration logs, and interpreted in the text of this report. Note that the observation periods were relatively short, and project planning can expect groundwater levels to fluctuate in response to rainfall, flooding, irrigation, seasonal freezing and thawing, surface drainage modifications and other seasonal and annual factors.



## **D.2. Continuity of Professional Responsibility**

### **D.2.a. Plan Review**

We based this report on a limited amount of information, and we made a number of assumptions to help us develop our recommendations. We should be retained to review the geotechnical aspects of the designs and specifications. This review will allow us to evaluate whether we anticipated the design correctly, if any design changes affect the validity of our recommendations, and if the design and specifications correctly interpret and implement our recommendations.

### **D.2.b. Construction Observations and Testing**

We recommend retaining us to perform the required observations and testing during construction as part of the ongoing geotechnical evaluation. This will allow us to correlate the subsurface conditions exposed during construction with those encountered by the borings and provide professional continuity from the design phase to the construction phase. If we do not perform observations and testing during construction, it becomes the responsibility of others to validate the assumption made during the preparation of this report and to accept the construction-related geotechnical engineer-of-record responsibilities.

## **D.3. Use of Report**

This report is for the exclusive use of the addressed parties. Without written approval, we assume no responsibility to other parties regarding this report. Our evaluation, analyses and recommendations may not be appropriate for other parties or projects.


## **D.4. Standard of Care**

In performing its services, Braun Intertec used that degree of care and skill ordinarily exercised under similar circumstances by reputable members of its profession currently practicing in the same locality. No warranty, express or implied, is made.

## **Appendix**



 **DENOTES APPROXIMATE LOCATION OF  
STANDARD PENETRATION TEST BORING**



11001 Hampshire Avenue S  
Minneapolis, MN 55438  
952.995.2000  
braunintertec.com

Project No:  
B1900033

Drawing No:  
B1900033


Drawn By: LAO  
Date Drawn: 2/25/19  
Checked By: EE  
Last Modified: 2/25/19

Geotechnical Evaluation

Bismarck Landfill Sand Exploration

Bismarck, North Dakota

**Soil Boring  
Location Sketch**



**Fence Diagram**  
(Horizontal distance not to scale)

**Braun Project B1900033**  
Geotechnical Evaluation  
Bismarck Landfill Sand Exploration  
2111 N 52nd St  
Bismarck, North Dakota

**BRAUN**<sup>SM</sup>  
**INTERTEC**

(See Descriptive Terminology sheet for explanation of abbreviations)

LOG OF BORING N:\GINT\PROJECTS\AX PROJECTS\2019\00033.GPJ BRAUN\_V8\_CURRENT.GDT 3/11/19 14:40

Braun Project B1900033 Geotechnical Evaluation Bismarck Landfill Sand Exploration 2111 N 52nd St Bismarck, North Dakota					BORING: <b>ST-01</b>		
DRILLER: A.Horner			METHOD: 3 1/4" HSA, Autohammer		DATE: 1/10/19		SCALE: 1" = 4'
Elev. feet	Depth feet	Symbol	Description of Materials (Soil-ASTM D2488 or D2487, Rock-USACE EM1110-1-2908)	BPF	WL	MC %	Tests or Notes
1771.6	0.0						
1771.1	0.5	TS SM	CLAYEY SAND, trace roots and Gravel, dark brown, frozen (moist when thawed). (Topsoil)	FA			Frost encountered to 2 feet.
1769.6	2.0	CLST	SILTY SAND, trace roots, little Gravel, calcification, and iron staining, brown, frozen (dry when thawed). (Glacial Outwash)	14			Boring elevations provided by Houston Engineering from surveying onsite.
			CANNONBALL FORMATION, CLAYSTONE, trace iron staining, interbedded Siltstone, brown, dry, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".	16			
1765.6	6.0	SS	CANNONBALL FORMATION, SANDSTONE, fine-grained, brown to gray, moist to wet, decomposed, very soft, sample retrieved as non-cemented "Poorly Graded Sand with Silt (SP-SM)".	30			
				36			
				47		1	
				54			*50/2".
				*			
				53			
				54			
				55			
1744.6	27.0	CLST	CANNONBALL FORMATION, CLAYSTONE, trace iron staining, interbedded with Siltstone, gray, moist, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".	24			An open triangle in the water level (WL) column indicates the depth at which groundwater was observed while drilling. A solid triangle indicates the groundwater level in the boring on the date indicated. Groundwater levels fluctuate.
				14			

(See Descriptive Terminology sheet for explanation of abbreviations)

LOG OF BORING N:\GINT\PROJECTS\AX\PROJECTS\2019\00033.GPJ BRAUN\_V8\_CURRENT.GDT 3/11/19 14:40

<b>Braun Project B1900033</b> <b>Geotechnical Evaluation</b> <b>Bismarck Landfill Sand Exploration</b> <b>2111 N 52nd St</b> <b>Bismarck, North Dakota</b>					<b>BORING: ST-01 (cont.)</b> <b>LOCATION: 46.830178, -100.701763, See sketch</b>		
<b>DRILLER:</b> A.Horner		<b>METHOD:</b> 3 1/4" HSA, Autohammer		<b>DATE:</b> 1/10/19		<b>SCALE:</b> 1" = 4'	
Elev. feet	Depth feet	Symbol	Description of Materials (Soil-ASTM D2488 or D2487, Rock-USACE EM1110-1-2908)	BPF	WL	MC %	Tests or Notes
1739.6	32.0		CANNONBALL FORMATION, CLAYSTONE, trace iron staining, interbedded with Siltstone, gray, moist, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)". <i>(continued)</i>	<div style="text-align: center;">21</div>	<div style="text-align: center;">▼</div>		
1720.6	51.0		END OF BORING.  Water observed at a depth of 29 1/2 feet while drilling.  Water observed at a depth of 39 feet with 49 1/2 feet of hollow-stem auger in the ground.  Water not observed to cave-in depth of 24 feet immediately after withdrawal of auger.  Boring then backfilled with bentonite chips to 1 foot below the surface. Auger cuttings used to backfill remainder of the boring.	<div style="text-align: center;">41</div> <div style="text-align: center;">33</div> <div style="text-align: center;">33</div>			

(See Descriptive Terminology sheet for explanation of abbreviations)

LOG OF BORING N:\GINT\PROJECTS\AX PROJECTS\2019\00033.GPJ BRAUN\_V8\_CURRENT.GDT 3/11/19 14:40

Braun Project B1900033 Geotechnical Evaluation Bismarck Landfill Sand Exploration 2111 N 52nd St Bismarck, North Dakota					BORING: <b>ST-02</b>		
DRILLER: A.Horner			METHOD: 3 1/4" HSA, Autohammer		DATE: 1/20/19		SCALE: 1" = 4'
Elev. feet	Depth feet	Symbol	Description of Materials (Soil-ASTM D2488 or D2487, Rock-USACE EM1110-1-2908)	BPF	WL	MC %	Tests or Notes
1781.2	0.0						
1780.7	0.5	TS SM	CLAYEY SAND, trace roots, dark brown, frozen (moist when thawed). (Topsoil)	FA			Frost encountered to 2 feet.
1779.2	2.0	CLST	SILTY SAND, trace roots and calcification, brown, frozen (moist when thawed). (Glacial Outwash)	49			
			CANNONBALL FORMATION, CLAYSTONE, trace iron staining, interbedded Siltstone, brown, dry, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".	29			
				28			
				23		23	
				21			
				23		20	
				48			
1760.2	21.0	SS	CANNONBALL FORMATION, SANDSTONE, fine-grained, brown to gray, moist to wet, decomposed, very soft, sample retrieved as non-cemented "Poorly Graded Sand with Silt (SP-SM)".	47			
				*			*50/5".
				*			*50/4".



(See Descriptive Terminology sheet for explanation of abbreviations)

LOG OF BORING N:\GINT\PROJECTS\AX PROJECTS\2019\00033.GPJ BRAUN\_V8\_CURRENT.GDT 3/11/19 14:40

<b>Braun Project B1900033</b> <b>Geotechnical Evaluation</b> <b>Bismarck Landfill Sand Exploration</b> <b>2111 N 52nd St</b> <b>Bismarck, North Dakota</b>					<b>BORING: ST-02 (cont.)</b> <b>LOCATION: 46.830202, -100.699970, See sketch</b>		
<b>DRILLER: A.Horner</b>		<b>METHOD: 3 1/4" HSA, Autohammer</b>		<b>DATE: 1/20/19</b>		<b>SCALE: 1" = 4'</b>	
Elev. feet	Depth feet	Symbol	Description of Materials (Soil-ASTM D2488 or D2487, Rock-USACE EM1110-1-2908)	BPF	WL	MC %	Tests or Notes
1749.2	32.0		CANNONBALL FORMATION, SANDSTONE, fine-grained, brown to gray, moist to wet, decomposed, very soft, sample retrieved as non-cemented "Poorly Graded Sand with Silt (SP-SM)". <i>(continued)</i>	*	▽		*50/3".
1743.2	38.0	CLST	CANNONBALL FORMATION, CLAYSTONE, interbedded with Siltstone, brown and gray, moist, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".	38	▼	26	
1730.2	51.0		END OF BORING.  Water observed at a depth of 34 1/2 feet while drilling.  Water observed at a depth of 39 feet with a cave-in depth of 34 feet immediately after withdrawal of auger.  Boring then backfilled with bentonite chips to 16 feet below the surface. Auger cuttings used to backfill remainder of the boring.	23			



(See Descriptive Terminology sheet for explanation of abbreviations)

LOG OF BORING N:\GINT\PROJECTS\AX PROJECTS\2019\00033.GPJ BRAUN\_V8\_CURRENT.GDT 3/11/19 14:40

Braun Project B1900033 Geotechnical Evaluation Bismarck Landfill Sand Exploration 2111 N 52nd St Bismarck, North Dakota					BORING: <b>ST-03</b>		
DRILLER: A.Horner			METHOD: 3 1/4" HSA, Autohammer		DATE: 1/14/19		SCALE: 1" = 4'
Elev. feet	Depth feet	Symbol	Description of Materials (Soil-ASTM D2488 or D2487, Rock-USACE EM1110-1-2908)	BPF	WL	MC %	Tests or Notes
1773.7	0.0						
1773.2	0.5	TS SM	CLAYEY SAND, trace roots, dark brown, frozen (moist when thawed). (Topsoil)	FA			Frost encountered to 2 feet.
			SILTY SAND, trace roots and calcification, brown, frozen (dry when thawed), very dense to medium dense. (Glacial Outwash)	55			
				30			
1767.7	6.0	CLST	CANNONBALL FORMATION, CLAYSTONE, trace iron staining, interbedded with Siltstone, brown, dry, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".	53		22	
				36			
				38		25	
1759.7	14.0	SS	CANNONBALL FORMATION, SANDSTONE, fine-grained, brown and gray, moist to wet, decomposed, very soft, sample retrieved as non-cemented "Poorly Graded Sand with Silt (SP-SM)".	26			
				*			*50/5".
				44			
				54		17	P200=11%
				41			
				61			
				52			

(See Descriptive Terminology sheet for explanation of abbreviations)

LOG OF BORING N:\GINT\PROJECTS\AX PROJECTS\2019\00033.GPJ BRAUN\_V8\_CURRENT.GDT 3/11/19 14:40

<b>Braun Project B1900033</b> <b>Geotechnical Evaluation</b> <b>Bismarck Landfill Sand Exploration</b> <b>2111 N 52nd St</b> <b>Bismarck, North Dakota</b>					BORING: <b>ST-03 (cont.)</b> LOCATION: 46.829357, -100.701680, See sketch			
DRILLER: A.Horner		METHOD: 3 1/4" HSA, Autohammer		DATE: 1/14/19		SCALE: 1" = 4'		
Elev. feet	Depth feet	Symbol	Description of Materials (Soil-ASTM D2488 or D2487, Rock-USACE EM1110-1-2908)	BPF	WL	MC %	Tests or Notes	
1741.7	32.0							
1739.7	34.0	CLST	CANNONBALL FORMATION, CLAYSTONE, interbedded with Siltstone, gray, moist, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".	23				
				26		23		
				24				
				27		24		
1722.7	51.0			32				
			END OF BORING.  Water observed at a depth of 27 feet while drilling.  Water not observed to cave-in depth of 49 1/2 feet immediately after withdrawal of auger.  Boring then backfilled with bentonite chips to 9 feet below the surface. Auger cuttings used to backfill remainder of the boring.					

(See Descriptive Terminology sheet for explanation of abbreviations)

LOG OF BORING N:\GINT\PROJECTS\AX PROJECTS\2019\00033.GPJ BRAUN\_V8\_CURRENT.GDT 3/11/19 14:40

Braun Project B1900033 Geotechnical Evaluation Bismarck Landfill Sand Exploration 2111 N 52nd St Bismarck, North Dakota					BORING: <b>ST-04</b>		
DRILLER: A.Horner			METHOD: 3 1/4" HSA, Autohammer		DATE: <b>2/20/19</b>		SCALE: <b>1" = 4'</b>
Elev. feet	Depth feet	Symbol	Description of Materials (Soil-ASTM D2488 or D2487, Rock-USACE EM1110-1-2908)	BPF	WL	MC %	Tests or Notes
1790.8	0.0						
1790.3	0.5	TS CLST	CLAYEY SAND, trace roots, dark brown, frozen (moist when thawed). (Topsoil) CANNONBALL FORMATION, CLAYSTONE, trace iron staining, interbedded Siltstone, brown, frozen (moist when thawed) to moist, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".	FA			Frost encountered to 4 feet.
				20		18	LL=63, PL=21, PI=42
				19			
				21		32	LL=84, PL=26, PI=58
1772.8	18.0	SS	CANNONBALL FORMATION, SANDSTONE, fine-grained, interbedded Claystone, brown, moist, decomposed, very soft, sample retrieved as non-cemented "Silty Sand (SM)".	24			
1767.8	23.0	CLST	CANNONBALL FORMATION, CLAYSTONE, interbedded Siltstone, trace mineralization and iron staining, brown, moist, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".	26		25	
1760.8	30.0	SS		30			Gradation performed from bag sample taken from 30 to 40 feet.

(See Descriptive Terminology sheet for explanation of abbreviations)

LOG OF BORING N:\GINT\PROJECTS\AX PROJECTS\2019\00033.GPJ BRAUN\_V8\_CURRENT.GDT 3/11/19 14:40

<b>Braun Project B1900033</b> <b>Geotechnical Evaluation</b> <b>Bismarck Landfill Sand Exploration</b> <b>2111 N 52nd St</b> <b>Bismarck, North Dakota</b>					BORING: <b>ST-04 (cont.)</b>		
					LOCATION: 46.829376, -100.700082, See sketch		
DRILLER: A.Horner		METHOD: 3 1/4" HSA, Autohammer		DATE: <b>2/20/19</b>		SCALE: <b>1" = 4'</b>	
Elev. feet	Depth feet	Symbol	Description of Materials (Soil-ASTM D2488 or D2487, Rock-USACE EM1110-1-2908)	BPF	WL	MC %	Tests or Notes
1758.8	32.0		CANNONBALL FORMATION, SANDSTONE, fine-grained, brown to gray, moist to wet, decomposed, very soft, sample retrieved as non-cemented "Silty Sand (SM)". <i>(continued)</i>	*			*50/5".
				75			
				*	▼		*50/2".
					▽		
				49			
				*			*50/3".
				87			
1743.8	47.0	CLST	CANNONBALL FORMATION, CLAYSTONE, interbedded Siltstone, gray, moist, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".	35			
1739.8	51.0		END OF BORING.	41			
Water observed at a depth of 39 1/2 feet while drilling.  A piezometer with a screen depth interval of 41 to 51 feet was set in the borehole.  On February 25 2019 water level was observed at 38 feet in piezometer.							

(See Descriptive Terminology sheet for explanation of abbreviations)

LOG OF BORING N:\GINT\PROJECTS\AX PROJECTS\2019\00033.GPJ BRAUN\_V8\_CURRENT.GDT 3/11/19 14:40

Braun Project B1900033 Geotechnical Evaluation Bismarck Landfill Sand Exploration 2111 N 52nd St Bismarck, North Dakota				BORING: ST-05 LOCATION: 46.828495, -100.701712 See sketch			
DRILLER: A.Horner		METHOD: 3 1/4" HSA, Autohammer		DATE: 1/10/19		SCALE: 1" = 4'	
Elev. feet	Depth feet	Symbol	Description of Materials (Soil-ASTM D2488 or D2487, Rock-USACE EM1110-1-2908)	BPF	WL	MC %	Tests or Notes
1774.3	0.0	TS	CLAYEY SAND, trace Gravel and roots, dark brown, frozen (moist when thawed). (Topsoil)	FA			Frost encountered to 2 feet.
1773.8	0.5	SM					
1770.3	4.0	CLST	CANNONBALL FORMATION, CLAYSTONE, trace iron staining and mineralization, interbedded Siltstone, brown, moist, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".	9		23	
				15			
				14		29	
1762.3	12.0	SS	CANNONBALL FORMATION, SANDSTONE, fine-grained, interbedded Claystone, trace iron staining, brown, moist, decomposed, very soft, sample retrieved as non-cemented "Silty Sand (SM)".	16			
1760.3	14.0	CLST	CANNONBALL FORMATION, CLAYSTONE, trace iron stianing and mineralization, interbedded with Siltstone, brown, moist, dense, very soft, hand deformed sample classified as "Fat Clay (CH)".	20			
				18			
			-with Sandstone seams at 20 feet.	24			
1752.3	22.0	SS	CANNONBALL FORMATION, SANDSTONE, fine-grained, trace iron staining, gray, moist to wet, decomposed, very soft, sample retrieved as non-cemented "Poorly Graded Sand with Silt (SP-SM)".	*		*50/3".	
				*		*50/6".	
				*		*50/6".	
				*		*50/6".	

(See Descriptive Terminology sheet for explanation of abbreviations)

LOG OF BORING N:\GINT\PROJECTS\AX\PROJECTS\2019\00033.GPJ BRAUN\_V8\_CURRENT.GDT 3/11/19 14:40

<b>Braun Project B1900033</b> <b>Geotechnical Evaluation</b> <b>Bismarck Landfill Sand Exploration</b> <b>2111 N 52nd St</b> <b>Bismarck, North Dakota</b>						<b>BORING: ST-05 (cont.)</b> <b>LOCATION: 46.828495, -100.701712 See sketch</b>			
<b>DRILLER: A.Horner</b>			<b>METHOD: 3 1/4" HSA, Autohammer</b>			<b>DATE: 1/10/19</b>		<b>SCALE: 1" = 4'</b>	
Elev. feet	Depth feet	Symbol	Description of Materials (Soil-ASTM D2488 or D2487, Rock-USACE EM1110-1-2908)	BPF	WL	MC %	Tests or Notes		
1742.3	32.0		<b>CANNONBALL FORMATION, SANDSTONE,</b> fine-grained, trace iron staining, gray, moist to wet, decomposed, very soft, sample retrieved as non-cemented "Poorly Graded Sand with Silt (SP-SM)". <i>(continued)</i>	*			*50/5".		
				*			*50/5".		
				*			*50/2".		
				49					
1732.3	42.0	CLST	<b>CANNONBALL FORMATION, CLAYSTONE,</b> interbedded with Siltstone, gray, moist, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".  -with Sandstone seam at 45 feet.	43					
				29					
1723.3	51.0		<b>END OF BORING.</b>  Water observed at a depth of 27 feet while drilling.  Water observed at a depth of 32 feet with 49 1/2 feet of hollow-stem auger in the ground.  Water not observed to cave-in depth of 21 feet immediately after withdrawal of auger.  Boring then backfilled with bentonite chips to 17 feet below the surface. Auger cuttings used to backfill remainder of the boring.	30					

(See Descriptive Terminology sheet for explanation of abbreviations)

LOG OF BORING N:\GINT\PROJECTS\AX\PROJECTS\2019\00033.GPJ BRAUN\_V8\_CURRENT.GDT 3/11/19 14:40


Braun Project B1900033 Geotechnical Evaluation Bismarck Landfill Sand Exploration 2111 N 52nd St Bismarck, North Dakota				BORING: ST-06 LOCATION: 46.828523, -100.700297 See sketch			
DRILLER: A.Horner		METHOD: 3 1/4" HSA, Autohammer		DATE: 1/18/19		SCALE: 1" = 4'	
Elev. feet	Depth feet	Symbol	Description of Materials (Soil-ASTM D2488 or D2487, Rock-USACE EM1110-1-2908)	BPF	WL	MC %	Tests or Notes
1781.4	0.0	TS SM	CLAYEY SAND, trace roots, dark brown, frozen (moist when thawed). (Topsoil)	FA			Frost encountered to 2 feet.
1780.9	0.5		SILTY SAND, trace calcification and roots, brown, frozen (dry when thawed) to moist, dense. (Glacial Outwash)	50			
1776.4	5.0	CLST	CANNONBALL FORMATION, CLAYSTONE, trace iron staining, interbedded Siltstone, brown, moist, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".	31		25	
				32			
				18			
				25			
				22			
				23			
				26			
		28	25				
1757.4	24.0	SS		CANNONBALL FORMATION, SANDSTONE, fine-grained, brown and gray, moist to wet, decomposed, very soft, sample retrieved as non-cemented "Silty Sand (SM)".	*		*50/5".
					*		
			58				

Braun Project B1900033 Geotechnical Evaluation Bismarck Landfill Sand Exploration 2111 N 52nd St Bismarck, North Dakota					BORING: ST-06 (cont.) LOCATION: 46.828523, -100.700297 See sketch			
DRILLER: A.Horner			METHOD: 3 1/4" HSA, Autohammer		DATE: 1/18/19		SCALE: 1" = 4'	
Elev. feet 1749.4	Depth feet 32.0	Symbol	Description of Materials (Soil-ASTM D2488 or D2487, Rock-USACE EM1110-1-2908)		BPF	WL	MC %	Tests or Notes
			CANNONBALL FORMATION, SANDSTONE, fine-grained, brown and gray, moist to wet, decomposed, very soft, sample retrieved as non-cemented "Silty Sand (SM)". (continued)		*			*50/5".
					78			
					88		25	P200=14%
					82			
					76			
					67			
1734.4	47.0							
		CLST	CANNONBALL FORMATION, CLAYSTONE, interbedded with Siltstone, gray, moist, decomposed, very soft, hand deformed sample classified as "Fat Clay (CH)".		38		22	
					45			
1730.4	51.0							
			END OF BORING.  Water observed at a depth of 32 feet while drilling.  Water not observed to cave-in depth of 49 1/2 feet immediately after withdrawal of auger.  Boring then backfilled with bentonite chips to 19 feet below the surface. Auger cuttings used to backfill remainder of the boring.					



Criteria for Assigning Group Symbols and Group Names Using Laboratory Tests <sup>A</sup>					Soil Classification	
					Group Symbol	Group Name <sup>B</sup>
Coarse-grained Soils (more than 50% retained on No. 200 sieve)	Gravels (More than 50% of coarse fraction retained on No. 4 sieve)	Clean Gravels (Less than 5% fines <sup>C</sup> )	$C_u \geq 4$ and $1 \leq C_c \leq 3^D$	GW	Well-graded gravel <sup>E</sup>	
			$C_u < 4$ and/or ( $C_c < 1$ or $C_c > 3$ ) <sup>D</sup>	GP	Poorly graded gravel <sup>E</sup>	
		Gravels with Fines (More than 12% fines <sup>C</sup> )	Fines classify as ML or MH	GM	Silty gravel <sup>EFG</sup>	
			Fines Classify as CL or CH	GC	Clayey gravel <sup>EFG</sup>	
	Sands (50% or more coarse fraction passes No. 4 sieve)	Clean Sands (Less than 5% fines <sup>H</sup> )	$C_u \geq 6$ and $1 \leq C_c \leq 3^D$	SW	Well-graded sand <sup>I</sup>	
			$C_u < 6$ and/or ( $C_c < 1$ or $C_c > 3$ ) <sup>D</sup>	SP	Poorly graded sand <sup>I</sup>	
		Sands with Fines (More than 12% fines <sup>H</sup> )	Fines classify as ML or MH	SM	Silty sand <sup>FGI</sup>	
			Fines classify as CL or CH	SC	Clayey sand <sup>FGI</sup>	
Fine-grained Soils (50% or more passes the No. 200 sieve)	Silts and Clays (Liquid limit less than 50)	Inorganic	PI > 7 and plots on or above "A" line <sup>J</sup>	CL	Lean clay <sup>KLM</sup>	
			PI < 4 or plots below "A" line <sup>J</sup>	ML	Silt <sup>KLM</sup>	
		Organic	Liquid Limit – oven dried Liquid Limit – not dried < 0.75	OL	Organic clay <sup>KLMN</sup> Organic silt <sup>KLMQ</sup>	
	Silts and Clays (Liquid limit 50 or more)	Inorganic	PI plots on or above "A" line	CH	Fat clay <sup>KLM</sup>	
			PI plots below "A" line	MH	Elastic silt <sup>KLM</sup>	
		Organic	Liquid Limit – oven dried Liquid Limit – not dried < 0.75	OH	Organic clay <sup>KLMP</sup> Organic silt <sup>KLMQ</sup>	
Highly Organic Soils		Primarily organic matter, dark in color, and organic odor			PT	Peat

- A. Based on the material passing the 3-inch (75-mm) sieve.  
B. If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.  
C. Gravels with 5 to 12% fines require dual symbols:  
GW-GM well-graded gravel with silt  
GW-GC well-graded gravel with clay  
GP-GM poorly graded gravel with silt  
GP-GC poorly graded gravel with clay  
D.  $C_u = D_{60} / D_{10}$   $C_c = (D_{30})^2 / (D_{10} \times D_{60})$   
E. If soil contains  $\geq 15\%$  sand, add "with sand" to group name.  
F. If fines classify as CL-ML, use dual symbol GC-GM or SC-SM.  
G. If fines are organic, add "with organic fines" to group name.  
H. Sands with 5 to 12% fines require dual symbols:  
SW-SM well-graded sand with silt  
SW-SC well-graded sand with clay  
SP-SM poorly graded sand with silt  
SP-SC poorly graded sand with clay  
I. If soil contains  $\geq 15\%$  gravel, add "with gravel" to group name.  
J. If Atterberg limits plot in hatched area, soil is CL-ML, silty clay.  
K. If soil contains 15 to < 30% plus No. 200, add "with sand" or "with gravel", whichever is predominant.  
L. If soil contains  $\geq 30\%$  plus No. 200, predominantly sand, add "sandy" to group name.  
M. If soil contains  $\geq 30\%$  plus No. 200 predominantly gravel, add "gravelly" to group name.  
N.  $PI \geq 4$  and plots on or above "A" line.  
O.  $PI < 4$  or plots below "A" line.  
P. PI plots on or above "A" line.  
Q. PI plots below "A" line



Laboratory Tests			
DD	Dry Density, pcf	OC	Organic content, %
WD	Wet Density, pcf	$q_p$	Pocket penetrometer strength
P200	% Passing #200 sieve	MC	Moisture content, %

## Particle Size Identification

Boulders..... over 12"  
Cobbles..... 3" to 12"  
Gravel  
Coarse..... 3/4" to 3" (19.00 mm to 75.00 mm)  
Fine..... No. 4 to 3/4" (4.75 mm to 19.00 mm)  
Sand  
Coarse..... No. 10 to No. 4 (2.00 mm to 4.75 mm)  
Medium..... No. 40 to No. 10 (0.425 mm to 2.00 mm)  
Fine..... No. 200 to No. 40  
(0.075 mm to 0.425 mm)  
Silt..... No. 200 (0.075 mm) to .005 mm  
Clay..... < .005 mm

## Relative Proportions<sup>L, M</sup>

trace..... 0 to 5%  
little..... 6 to 14%  
with.....  $\geq 15\%$

## Inclusion Thicknesses

lens..... 0 to 1/8"  
seam..... 1/8" to 1"  
layer..... over 1"

## Apparent Relative Density of Cohesionless Soils

Very loose ..... 0 to 4 BPF  
Loose ..... 5 to 10 BPF  
Medium dense..... 11 to 30 BPF  
Dense..... 31 to 50 BPF  
Very dense..... over 50 BPF

Consistency of Cohesive Soils	Blows Per Foot	Approximate Unconfined Compressive Strength
Very soft.....	0 to 1 BPF.....	< 1/4 tsf
Soft.....	2 to 4 BPF.....	1/4 to 1/2 tsf
Medium.....	5 to 8 BPF.....	1/2 to 1 tsf
Stiff.....	9 to 15 BPF.....	1 to 2 tsf
Very Stiff.....	16 to 30 BPF.....	2 to 4 tsf
Hard.....	over 30 BPF.....	> 4 tsf

## Moisture Content:

**Dry:** Absence of moisture, dusty, dry to the touch.  
**Moist:** Damp but no visible water.  
**Wet:** Visible free water, usually soil is below water table.

## Drilling Notes:


**BPF:** Numbers indicate blows per foot recorded in standard penetration test, also known as "N" value. The sampler was set 6 inches into undisturbed soil below the hollow-stem auger. Driving resistances were then counted for second and third 6-inch increments, and added to get BPF.

**Partial Penetration:** If the sampler cannot be driven the full 12 inches beyond the initial 6-inch set, the number of blows for that partial penetration is shown as "No./X" (i.e., 50/2"). If the sampler cannot be advanced beyond the initial 6-inch set, the depth of penetration will be recorded in the Notes column as "No. to set X" (i.e., 50 to set 4").

**WH:** WH indicates the sampler penetrated soil under weight of hammer and rods alone; driving not required.

**WR:** WR indicates the sampler penetrated soil under weight of rods alone; hammer weight and driving not required.

**WL:** WL indicates the water level measured by the drillers either while drilling or following drilling.



### Example Calculations

Core Recovery, CR =  $\frac{\text{Total length of rock recovered}}{\text{Total core run length}}$

Example:  $CR = \frac{(18 + 6 + 13 + 9 + 2 + 3 + 3)}{(60)}$

$CR = 90\%$

RQD =  $\frac{\text{Sum of sound pieces 4 inches or larger}}{\text{Total core run length}}$

RQD Percent	Rock Quality
< 25	very poor
25 < 50	poor
50 < 75	fair
75 < 90	good
90 < 100	excellent

Example:  $RQD = \frac{(18 + 9 + 6)}{(60)}$

$RQD = 55\%$

### Weathering

**Unweathered:** No evidence of chemical or mechanical alteration.

**Slightly weathered:** Slight discoloration on surface, slight alteration along discontinuities, less than 10% of rock volume altered.

**Moderately Weathered:** Discoloration evident, surface pitted and altered with alteration penetrating well below rock surfaces, weathering halos evident, 10% to 50% of the rock altered.

**Highly Weathered:** Entire mass discolored, alteration pervading nearly all of the rock, with some pockets of slightly weathered rock noticeable, some mineral leached away.

**Decomposed:** Rock reduced to a soil consistency with relict rock texture, generally molded and crumbled by hand.

### Hardness

<b>Very soft:</b>	Can be deformed by hand
<b>Soft:</b>	Can be scratched with a fingernail
<b>Moderately hard:</b>	Can be scratched easily with a knife
<b>Hard:</b>	Can be scratched with difficulty with a knife
<b>Very hard:</b>	Cannot be scratched with a knife

### Texture

Sedimentary Rocks:	Grain Size
Coarse grained	2 – 5 mm
Medium grained	0.4 – 2 mm
Fine grained	0.1 – 0.4 mm
Very fine grained	< 0.1 mm

### Igneous and Metamorphic Rocks:

Coarse grained	5 mm
Medium grained	1 – 5 mm
Fine grained	0.1 – 1 mm
Aphanitic	< 0.1 mm

### Thickness of Bedding


<b>Massive:</b>	3 ft. thick or greater
<b>Thick bedded:</b>	1 to 3 ft. thick
<b>Medium bedded:</b>	4 in. to 1 ft. thick
<b>Thin bedded:</b>	4 in. thick or less

### Degree of Fracturing (Jointing)

<b>Unfractured:</b>	Fracture spacing 6 ft. or more
<b>Slightly fractured:</b>	Fracture spacing 2 to 6 ft.
<b>Moderately fractured:</b>	Fracture spacing 8 in. to 2 ft.
<b>Highly fractured:</b>	Fracture spacing 2 in. to 8 in.
<b>Intensely fractured:</b>	Fracture spacing 2 in. or less

GRAIN SIZE ACCUMULATION CURVE (ASTM)

GRAVEL		SAND			FINES	
COARSE	FINE	COARSE	MEDIUM	FINE	SILT	CLAY



	<b>Braun Project B1900033</b> Geotechnical Evaluation Bismarck Landfill Sand Exploration 2111 N 52nd St Bismarck, North Dakota BORING: ST-04 DEPTH: 35.0'		<b>CLASSIFICATION:</b> Silty Sand (SM)
	GRAVEL SAND FINES	0.0% 65.8% 34.2%	$C_u =$ $C_c =$

**ATTACHMENT  
NO. 3  
COMPLIANCE TESTING  
RESULTS FROM THE 2020  
EXCAVATION PHASE - CITY  
PROJECT # LF 2020-001**



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## ATTERBERG LIMITS' RESULTS


ASTM D4318

Report To: RJ Zavoral and Sons  
1706 Bygland Rd SE  
East Grand Forks MN 56721  
Attention: Zach Bopp, PM

Project: Solid Waste Management Area Cell 1  
Project Number: 20.BIS09947.000  
Location: Bismarck Landfill  
Bismarck, ND

### Sample Data

SAMPLE #	LL	PL	PI	Fines	Classification
● P-1	70	39	31	54	SANDY FAT CLAY, BROWN
☒ P-2	46	35	11	52	SANDY LEAN CLAY, LIGHT BROWN TO GRAY
▲ P-3	66	40	26	65	SANDY FAT CLAY, LIGHT BROWN TO GRAY
★ P-4	56	34	22	66	SANDY FAT CLAY, BROWN
⊙ P-5	75	26	49	57	SANDY FAT CLAY, LIGHT BROWN TO GRAY



Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(4/23/20)




**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
**www.NTIgeo.com**

## ASTM D4318

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721
Attention:	Zach Bopp, PM

Project:	Solid Waste Management Area Cell 1
Project Number:	20.BIS09947.000
Location:	Bismarck Landfill Bismarck, ND

[illegible]

Cc:

Submitted by,  
***Northern Technologies, LLC***

Tyler T Hall

Tyler Hall  
(6/3/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 1 OF 2

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*	Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max									Density	Moisture
1	4/1/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 51+00	90		-3	3	B 1780.59	P-1	127.5	19.7	106.5	104.6	19.9	101.8	Pass	Pass
2	4/1/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 55+00	90		-3	3	B 1790.37	P-2	112.8	21.7	92.7	100.4	20.9	92.3	Pass	Pass
3	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 79+00, 10' RIGHT	90		-3	3	B 2	P-2	117.4	22.9	95.5	100.4	20.9	95.1	Pass	Pass
4	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 84+00, 10' LEFT	90		-3	3	B 2	P-2	120.0	21.8	98.5	100.4	20.9	98.1	Pass	Pass
5	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 10+00, 10' LEFT	90		-3	3	B 2	P-2	116.5	21.4	96.0	100.4	20.9	95.6	Pass	Pass
6	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 15+50, CENTER LINE	90		-3	3	B 2	P-2	116.6	23.9	94.1	100.4	20.9	93.7	Pass	Pass
7	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 72+50, CENTER LINE	90		-3	3	B 2	P-2	117.5	19.0	98.7	100.4	20.9	98.3	Pass	Pass
8	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 68+50, 20' RIGHT	90		-3	3	B 4	P-2	118.3	21.1	97.7	100.4	20.9	97.3	Pass	Pass
9	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 65+00, 20' LEFT	90		-3	3	B 4	P-2	121.9	23.7	98.5	100.4	20.9	98.1	Pass	Pass
10	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 58+00, 10' LEFT	90		-3	3	B 3	P-2	112.5	23.6	91.0	100.4	20.9	90.6	Pass	Pass

Comments:


Cc:

Submitted by,  
**Northern Technologies, LLC**

\* TEST ELEVATION

- A = Depth From Existing Ground Surface
- B = Depth From Project Datum
- C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

  
Tyler Hall  
(4/10/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 2 OF 2

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*		Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max										Density	Moisture
11	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 17+50, 15' RIGHT	90		-3	3	B	2	P-2	122.5	22.7	99.8	100.4	20.9	99.4	Pass	Pass

Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

**\* TEST ELEVATION**

- A = Depth From Existing Ground Surface
- B = Depth From Project Datum
- C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

Tyler Hall  
(4/10/20)





**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 1 OF 2

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*	Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max									Density	Moisture
1	4/1/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 51+00	90		-3	3	B 1780.59	P-1	127.5	19.7	106.5	104.6	19.9	101.8	Pass	Pass
2	4/1/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 55+00	90		-3	3	B 1790.37	P-2	112.8	21.7	92.7	100.4	20.9	92.3	Pass	Pass
3	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 79+00, 10' RIGHT	90		-3	3	B 2	P-2	117.4	22.9	95.5	100.4	20.9	95.1	Pass	Pass
4	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 84+00, 10' LEFT	90		-3	3	B 2	P-2	120.0	21.8	98.5	100.4	20.9	98.1	Pass	Pass
5	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 10+00, 10' LEFT	90		-3	3	B 2	P-2	116.5	21.4	96.0	100.4	20.9	95.6	Pass	Pass
6	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 15+50, CENTER LINE	90		-3	3	B 2	P-2	116.6	23.9	94.1	100.4	20.9	93.7	Pass	Pass
7	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 72+50, CENTER LINE	90		-3	3	B 2	P-2	117.5	19.0	98.7	100.4	20.9	98.3	Pass	Pass
8	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 68+50, 20' RIGHT	90		-3	3	B 4	P-2	118.3	21.1	97.7	100.4	20.9	97.3	Pass	Pass
9	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 65+00, 20' LEFT	90		-3	3	B 4	P-2	121.9	23.7	98.5	100.4	20.9	98.1	Pass	Pass
10	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 58+00, 10' LEFT	90		-3	3	B 3	P-2	112.5	23.6	91.0	100.4	20.9	90.6	Pass	Pass

Comments:


Cc:

Submitted by,  
**Northern Technologies, LLC**

\* TEST ELEVATION

- A = Depth From Existing Ground Surface
- B = Depth From Project Datum
- C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

  
Tyler Hall  
(4/10/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 2 OF 2

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*		Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max										Density	Moisture
11	4/6/2020	MASS GRADING, CELL #1. HAUL ROAD, STA 17+50, 15' RIGHT	90		-3	3	B	2	P-2	122.5	22.7	99.8	100.4	20.9	99.4	Pass	Pass

Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

**\* TEST ELEVATION**

- A = Depth From Existing Ground Surface
- B = Depth From Project Datum
- C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

Tyler Hall  
(4/10/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 1 OF 1

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*		Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max										Density	Moisture
12	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 73+00, 10' LEFT	90		-3	3	B	4	P-2	119.2	21.8	97.9	100.4	20.9	97.5	Pass	Pass
13	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 70+00, 15' RIGHT	90		-3	3	B	6	P-2	122.1	22.8	99.4	100.4	20.9	99.0	Pass	Pass
14	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 66+00, CENTER LINE	90		-3	3	B	6	P-2	119.4	23.0	97.1	100.4	20.9	96.7	Pass	Pass
15	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 61+00, 5' RIGHT	90		-3	3	B	6	P-2	113.5	21.4	93.5	100.4	20.9	93.1	Pass	Pass
16	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 55+00, 20' RIGHT	90		-3	3	B	4	P-2	121.6	22.3	99.4	100.4	20.9	99.0	Pass	Pass
17	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 48+00, 15' RIGHT	90		-3	3	B	4	P-1	121.8	18.2	103.0	104.6	19.9	98.5	Pass	Pass
18	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 79+00, 20' LEFT	90		-3	3	B	4	P-2	116.5	21.0	96.3	100.4	20.9	95.9	Pass	Pass
19	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 84+00, 15' LEFT	90		-3	3	B	4	P-2	121.6	20.7	100.7	100.4	20.9	100.3	Pass	Pass
20	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 11+00, 10' LEFT	90		-3	3	B	4	P-2	119.3	22.1	97.7	100.4	20.9	97.3	Pass	Pass
21	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 16+00, 20' LEFT	90		-3	3	B	4	P-2	118.4	23.7	95.7	100.4	20.9	95.3	Pass	Pass

Comments:

Cc:

Submitted by,

**Northern Technologies, LLC**

\* TEST ELEVATION

A = Depth From Existing Ground Surface

B = Depth From Project Datum

C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

Tyler Hall  
(4/10/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 1 OF 1

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*		Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max										Density	Moisture
12	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 73+00, 10' LEFT	90		-3	3	B	4	P-2	119.2	21.8	97.9	100.4	20.9	97.5	Pass	Pass
13	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 70+00, 15' RIGHT	90		-3	3	B	6	P-2	122.1	22.8	99.4	100.4	20.9	99.0	Pass	Pass
14	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 66+00, CENTER LINE	90		-3	3	B	6	P-2	119.4	23.0	97.1	100.4	20.9	96.7	Pass	Pass
15	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 61+00, 5' RIGHT	90		-3	3	B	6	P-2	113.5	21.4	93.5	100.4	20.9	93.1	Pass	Pass
16	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 55+00, 20' RIGHT	90		-3	3	B	4	P-2	121.6	22.3	99.4	100.4	20.9	99.0	Pass	Pass
17	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 48+00, 15' RIGHT	90		-3	3	B	4	P-1	121.8	18.2	103.0	104.6	19.9	98.5	Pass	Pass
18	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 79+00, 20' LEFT	90		-3	3	B	4	P-2	116.5	21.0	96.3	100.4	20.9	95.9	Pass	Pass
19	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 84+00, 15' LEFT	90		-3	3	B	4	P-2	121.6	20.7	100.7	100.4	20.9	100.3	Pass	Pass
20	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 11+00, 10' LEFT	90		-3	3	B	4	P-2	119.3	22.1	97.7	100.4	20.9	97.3	Pass	Pass
21	4/7/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 16+00, 20' LEFT	90		-3	3	B	4	P-2	118.4	23.7	95.7	100.4	20.9	95.3	Pass	Pass

Comments:


Cc:

Submitted by,  
**Northern Technologies, LLC**

\* TEST ELEVATION

- A = Depth From Existing Ground Surface
- B = Depth From Project Datum
- C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

  
Tyler Hall  
(4/10/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 1 OF 1

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*		Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max										Density	Moisture
22	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 10+00, CENTER LINE	90		-3	3	B	6	P-2	119.2	22.7	97.1	100.4	20.9	96.7	Pass	Pass
23	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 16+00, 10' LEFT	90		-3	3	B	6	P-2	118.6	20.7	98.3	100.4	20.9	97.9	Pass	Pass
24	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 72+00, 10' RIGHT	90		-3	3	B	6	P-2	120.7	22.2	98.8	100.4	20.9	98.4	Pass	Pass
25	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 68+00 15' RIGHT	90		-3	3	B	8	P-2	115.9	23.8	93.6	100.4	20.9	93.2	Pass	Pass
26	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 65+00, CENTER LINE	90		-3	3	B	8	P-2	119.4	21.5	98.3	100.4	20.9	97.9	Pass	Pass
27	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 61+00, 10' RIGHT	90		-3	3	B	8	P-1	123.9	18.1	104.9	104.6	19.9	100.3	Pass	Pass
28	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 53+00, CENTER LINE	90		-3	3	B	6	P-1	124.3	19.1	104.4	104.6	19.9	99.8	Pass	Pass
29	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 46+00, 10' RIGHT	90		-3	3	B	6	P-2	119.3	22.1	97.7	100.4	20.9	97.3	Pass	Pass

Comments:


Cc:

Submitted by,  
**Northern Technologies, LLC**

\* TEST ELEVATION

- A = Depth From Existing Ground Surface
- B = Depth From Project Datum
- C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

  
Tyler Hall  
(4/9/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 1 OF 1

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*		Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max										Density	Moisture
22	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 10+00, CENTER LINE	90		-3	3	B	6	P-2	119.2	22.7	97.1	100.4	20.9	96.7	Pass	Pass
23	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 16+00, 10' LEFT	90		-3	3	B	6	P-2	118.6	20.7	98.3	100.4	20.9	97.9	Pass	Pass
24	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 72+00, 10' RIGHT	90		-3	3	B	6	P-2	120.7	22.2	98.8	100.4	20.9	98.4	Pass	Pass
25	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 68+00 15' RIGHT	90		-3	3	B	8	P-2	115.9	23.8	93.6	100.4	20.9	93.2	Pass	Pass
26	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 65+00, CENTER LINE	90		-3	3	B	8	P-2	119.4	21.5	98.3	100.4	20.9	97.9	Pass	Pass
27	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 61+00, 10' RIGHT	90		-3	3	B	8	P-1	123.9	18.1	104.9	104.6	19.9	100.3	Pass	Pass
28	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 53+00, CENTER LINE	90		-3	3	B	6	P-1	124.3	19.1	104.4	104.6	19.9	99.8	Pass	Pass
29	4/8/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 46+00, 10' RIGHT	90		-3	3	B	6	P-2	119.3	22.1	97.7	100.4	20.9	97.3	Pass	Pass

Comments:


Cc:

Submitted by,  
**Northern Technologies, LLC**

\* TEST ELEVATION

- A = Depth From Existing Ground Surface
- B = Depth From Project Datum
- C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

  
Tyler Hall  
(4/9/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 1 OF 2

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*		Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max										Density	Moisture
30	4/14/2020	MASS GRADING, CELL #1, HAUL RAOD; STATION 96+00, CENTER LINE	90		-3	3	B	4	P-2	122.0	23.1	99.1	100.4	20.9	98.7	Pass	Pass
31	4/14/2020	MASS GRADING, CELL #1, HAUL RAOD; STATION 93+00, LEFT	90		-3	3	B	8	P-1	123.5	21.6	101.6	104.6	19.9	97.1	Pass	Pass
32	4/14/2020	MASS GRADING, CELL #1, HAUL RAOD; STATION 92+50, RIGHT	90		-3	3	B	6	P-2	117.2	23.5	94.9	100.4	20.9	94.5	Pass	Pass
33	4/14/2020	MASS GRADING, CELL #1, HAUL RAOD; STATION 91+00, CENTERLINE	90		-3	3	B	2	P-2	113.5	17.9	96.3	100.4	20.9	95.9	Pass	Pass
34	4/14/2020	MASS GRADING, CELL #1, HAUL RAOD; STATION 73+00, CENTERLINE	90		-3	3	B	@	P-2	119.1	19.5	99.7	100.4	20.9	99.3	Pass	Pass
35	4/14/2020	MASS GRADING, CELL #1, HAUL RAOD; STATION 67+00, LEFT	90		-3	3	B	@	P-2	112.5	18.1	95.3	100.4	20.9	94.9	Pass	Pass
36	4/14/2020	MASS GRADING, STORM WATER POND BOTTOM; EAST END	90		-3	3	B	@	P-2	111.8	21.8	91.8	100.4	20.9	91.4	Pass	Pass
37	4/14/2020	MASS GRADING, STORM WATER POND BOTTOM; SOUTH SIDE	90		-3	3	B	2	P-2	117.7	18.6	99.2	100.4	20.9	98.8	Pass	Pass
38	4/14/2020	MASS GRADING, STORM WATER POND BOTTOM; NORTH SIDE	90		-3	3	B	2	P-2	118.2	18.3	99.9	100.4	20.9	99.5	Pass	Pass
39	4/14/2020	MASS GRADING, CELL #1, HAUL ROAD; STATION 5+00, CENTERLINE	90		-3	3	B	4	P-1	122.7	20.2	102.1	104.6	19.9	97.6	Pass	Pass

Comments:

Cc:

Submitted by,

**Northern Technologies, LLC**

\* TEST ELEVATION

A = Depth From Existing Ground Surface

B = Depth From Project Datum

C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

Tyler Hall  
(4/21/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 2 OF 2

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*		Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max										Density	Moisture
40	4/14/2020	MASS GRADING, CELL #1, HAUL RAOD; STATION 2+00, LEFT	90		-3	3	B	2	P-1	122.8	20.9	101.6	104.6	19.9	97.1	Pass	Pass

Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

**\* TEST ELEVATION**

- A = Depth From Existing Ground Surface
- B = Depth From Project Datum
- C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

Tyler Hall  
(4/21/20)





**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 1 OF 2

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*		Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max										Density	Moisture
41	4/15/2020	MASS GRADING, CELL #1, STORM WATER POND; NORTH SIDE	90		-3	3	B	4	P-2	113.3	18.0	96.0	100.4	20.9	95.6	Pass	Pass
42	4/15/2020	MASS GRADING, CELL #1, STORM WATER POND; WEST END, BOTTOM	90		-3	3	B	@	P-2	113.9	20.4	94.6	100.4	20.9	94.2	Pass	Pass
43	4/15/2020	MASS GRADING, CELL #1, STORM WATER POND; SOUTH SIDE	90		-3	3	B	4	P-1	121.8	16.9	104.2	104.6	19.9	99.6	Pass	Pass
44	4/15/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 6+00, CENTERLINE	90		-3	3	B	6	P-1	122.5	17.1	104.6	104.6	19.9	100.0	Pass	Pass
45	4/15/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 12+00, LEFT	90		-3	3	B	8	P-1	113.1	19.1	95.0	104.6	19.9	90.8	Pass	Pass
46	4/17/2020	MASS GRADING, CELL #1, STORM WATER POND; NORTH EMBANKMENT, EAST END	90		-3	3	B	8	P-2	113.4	18.3	95.9	100.4	20.9	95.5	Pass	Pass
47	4/17/2020	MASS GRADING, CELL #1, STORM WATER POND; NORTH EMBANKMENT, WEST END	90		-3	3	B	6	P-2	110.9	19.5	92.8	100.4	20.9	92.4	Pass	Pass
48	4/17/2020	MASS GRADING, CELL #1, STORM WATER POND; SOUTH EMBANKMENT, EAST END	90		-3	3	B	8	P-1	119.1	17.5	101.4	104.6	19.9	96.9	Pass	Pass
49	4/17/2020	MASS GRADING, CELL #1, STORM WATER POND; SOUTH EMBANKMENT, WEST END	90		-3	3	B	6	P-2	118.2	18.2	100.0	100.4	20.9	99.6	Pass	Pass
50	4/17/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 43+00, CENTERLINE	90		-3	3	B	@	P-2	114.2	21.9	93.7	100.4	20.9	93.3	Pass	Pass

Comments:

Cc:

Submitted by,

**Northern Technologies, LLC**

\* TEST ELEVATION

A = Depth From Existing Ground Surface

B = Depth From Project Datum

C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

Tyler Hall

(4/22/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 2 OF 2

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*		Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max										Density	Moisture
51	4/17/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 106+00, CENTERLINE	90		-3	3	B	3	P-2	110.1	18.2	93.1	100.4	20.9	92.7	Pass	Pass
52	4/17/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 110+50, LEFT	90		-3	3	B	6	P-2	110.3	19.1	92.6	100.4	20.9	92.2	Pass	Pass
53	4/17/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 111+50, LEFT	90		-3	3	B	8	P-2	111.4	19.7	93.1	100.4	20.9	92.7	Pass	Pass
54	4/17/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 51+00, RIGHT	90		-3	3	B	@	P-2	116.2	19.6	97.2	100.4	20.9	96.8	Pass	Pass
55	4/17/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 16+00, RIGHT	90		-3	3	B	@	P-2	113.3	18.2	95.9	100.4	20.9	95.5	Pass	Pass
56	4/17/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 2+00, CENTERLINE	90		-3	3	B	@	P-2	119.6	23.2	97.1	100.4	20.9	96.7	Pass	Pass
57	4/20/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 83+00	90		-3	3	B	@	P-1	124.8	19.7	104.3	104.6	19.9	99.7	Pass	Pass
58	4/20/2020	MASS GRADING, CELL #1, HAUL ROAD; STA 78+00	90		-3	3	B	@	P-1	118.4	17.6	100.7	104.6	19.9	96.3	Pass	Pass
59	4/20/2020	STORM WATER POND; SOUTH EMBANKMENT, CENTER	90		-3	3	B	10	P-1	123.0	18.6	103.7	104.6	19.9	99.1	Pass	Pass
60	4/20/2020	STORM WATER POND; NORTH EMBANKMENT, CENTER	90		-3	3	B	@	P-2	111.8	18.1	94.7	100.4	20.9	94.3	Pass	Pass

Comments:


Cc:

Submitted by,  
**Northern Technologies, LLC**

\* TEST ELEVATION

- A = Depth From Existing Ground Surface
- B = Depth From Project Datum
- C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

  
Tyler Hall  
(4/22/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 1 OF 1

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*		Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max										Density	Moisture
61	4/23/2020	STORM SEWER BACKFILL; STATION 18+70	90		-3	3	B	3	P-2	113.4	18.9	95.4	100.4	20.9	95.0	Pass	Pass
62	4/23/2020	STORM SEWER BACKFILL; STATION 15+50	90		-3	3	B	3	P-2	113.9	19.4	95.4	100.4	20.9	95.0	Pass	Pass
63	4/23/2020	STORM SEWER BACKFILL; STATION 14+00	90		-3	3	B	3	P-2	114.6	17.9	97.2	100.4	20.9	96.8	Pass	Pass
64	4/23/2020	STORM SEWER BACKFILL; 40' WEST OF STORM POND OUTLET STRUCTURE	90		-3	3	B	3	P-1	120.2	17.7	102.1	104.6	19.9	97.6	Pass	Pass
65	4/23/2020	STORM SEWER BACKFILL; STATION 17+00	90		-3	3	B	6	P-1	120.6	17.0	103.1	104.6	19.9	98.6	Pass	Pass
66	4/23/2020	STORM SEWER BACKFILL; STATION 16+00	90		-3	3	B	6	P-1	117.1	17.1	100.0	104.6	19.9	95.6	Pass	Pass
67	4/23/2020	STORM SEWER BACKFILL; STATION 14+00	90		-3	3	B	6	P-1	117.3	16.9	100.3	104.6	19.9	95.9	Pass	Pass

Comments:


Cc:

Submitted by,  
**Northern Technologies, LLC**

\* TEST ELEVATION

- A = Depth From Existing Ground Surface
- B = Depth From Project Datum
- C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

  
Tyler Hall  
(4/24/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## DENSITY TEST OF SOIL

PAGE 1 OF 1

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	<b>Zach Bopp, PM</b>	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

Test No.	Test Date	Test Location	Compaction Criteria		Moisture Criteria		Test Elevation*		Proctor Mark	Moist Unit Weight (pcf)	Moisture Content (%)	Dry Unit Weight (pcf)	Maximum Unit Weight (pcf)	Optimum Moisture Content (%)	Percent Compaction	Requirements	
			Min	Max	Min	Max										Density	Moisture
68	4/29/2020	STORM SEWER BACKFILL; SOUTH DIKE	90		-3	3	B	@	P-2	111.1	18.0	94.2	100.4	20.9	93.8	Pass	Pass
69	4/29/2020	STORM SEWER BACKFILL; 20' EAST OF STORM POND OUTLET STRUCTURE	90		-3	3	B	-2	P-2	112.4	17.9	95.3	100.4	20.9	94.9	Pass	Pass
70	4/29/2020	STORM SEWER BACKFILL; STA 12+85	90		-3	3	B	3	P-2	110.4	19.0	92.8	100.4	20.9	92.4	Pass	Pass
71	4/29/2020	STORM SEWER BACKFILL; STA 11+60	90		-3	3	B	3	P-6	105.4	7.7	97.9	101.7	9.2	96.3	Pass	Pass
72	4/29/2020	STORM SEWER BACKFILL; STA 11+20	90		-3	3	B	3	P-6	112.2	11.4	100.7	101.7	9.2	99.0	Pass	Pass
73	4/29/2020	STORM SEWER BACKFILL; STA 1+00	90		-3	3	B	4	P-1	121.0	20.9	100.1	104.6	19.9	95.7	Pass	Pass
74	5/6/2020	STORM SEWER BACKFILL; STA 10+50	90		-3	3	B	4	P-6	112.4	29.5	86.8	101.7	9.2	85.3	Fail	Fail
75	5/6/2020	STORM SEWER BACKFILL; STA 10+70	90		-3	3	B	6	P-6	111.1	12.2	99.0	101.7	9.2	97.3	Pass	Pass
76	5/6/2020	STORM SEWER BACKFILL; STA 8+00	90		-3	3	B	8	P-6	105.5	7.3	98.3	101.7	9.2	96.7	Pass	Pass
77	5/6/2020	STORM SEWER BACKFILL; STA 4+50	90		-3	3	B	6	P-2	118.1	17.9	100.2	100.4	20.9	99.8	Pass	Pass

Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

\* TEST ELEVATION

- A = Depth From Existing Ground Surface
- B = Depth From Project Datum
- C = Depth From U.S.G.S. Datum

Test results shown above are limited to the given location, elevation, and date.

Tyler Hall  
(5/11/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## GRAIN SIZE DISTRIBUTION

ASTM C136 & D422

Report To: RJ Zavoral and Sons  
1706 Bygland Rd SE  
East Grand Forks MN 56721  
Attention: Zach Bopp, PM


Project: Solid Waste Management Area Cell 1  
Project Number: 20.BIS09947.000  
Location: Bismarck Landfill  
Bismarck, ND

### Sample Information

Sample Number:	1	Date Sampled:	4/15/2020
Project Specifications:	BISMARCK 801-2.8 BEDDING	Sampled By:	NTI
Aggregate Type:	SAND, FINE GRAINED		
Location Sampled:	EXISTING ON SITE MATERIAL FOR BEDDING (AS RECIEVED MOISTURE CONTENT = 7.8%)		

### Sample Data

Cc	Cu	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
1.26	2.38	50	0.22	0.16	0.093	2.0	94.0		4.1



Comments: SAMPLE DID NOT MEET PROJECT SPECIFICATIONS ON THE FOLLOWING SIEVES: #4, #30, AND #100

Cc:

Submitted by,  
**Northern Technologies, LLC**

*Tyler T Hall*  
Tyler Hall  
(5/1/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## GRAIN SIZE DISTRIBUTION

ASTM C136 & D422

Report To: RJ Zavoral and Sons  
1706 Bygland Rd SE  
East Grand Forks MN 56721  
Attention: Zach Bopp, PM


Project: Solid Waste Management Area Cell 1  
Project Number: 20.BIS09947.000  
Location: Bismarck Landfill  
Bismarck, ND

### Sample Information

Sample Number:	2	Date Sampled:	5/21/2020
Project Specifications:	CLASS #13	Sampled By:	NTI
Aggregate Type:	CLASS #13		
Location Sampled:	ND DOT CLASS 13 FROM SOURCE - KNIFE RIVER		

### Sample Data

Cc	Cu	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
		25	3.195	0.217		34.3	50.8		14.8



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(5/22/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## GRAIN SIZE DISTRIBUTION

ASTM C136 & D422

Report To: RJ Zavoral and Sons  
1706 Bygland Rd SE  
East Grand Forks MN 56721  
Attention: Zach Bopp, PM


Project: Solid Waste Management Area Cell 1  
Project Number: 20.BIS09947.000  
Location: Bismarck Landfill  
Bismarck, ND

### Sample Information

Sample Number:	3	Date Sampled:	5/28/2020
Project Specifications:		Sampled By:	NTI
Aggregate Type:	NDDOT CLASS 13, AGGREGATE BASE, FROM KNIFE RIVER		
Location Sampled:	HAUL ROAD AGGREGATE BASE AT STATION 92+00		

### Sample Data


Cc	Cu	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
0.54	97.86	25	6.279	0.466		46.6	42.0		11.4



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

  
Tyler Hall  
(6/5/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## GRAIN SIZE DISTRIBUTION

ASTM C136 & D422

Report To: RJ Zavoral and Sons  
1706 Bygland Rd SE  
East Grand Forks MN 56721  
Attention: Zach Bopp, PM


Project: Solid Waste Management Area Cell 1  
Project Number: 20.BIS09947.000  
Location: Bismarck Landfill  
Bismarck, ND

### Sample Information

Sample Number:	4	Date Sampled:	5/29/2020
Project Specifications:	NDDOT CLASS 13	Sampled By:	NTI
Aggregate Type:	NDDOT CLASS 13; AGGREGATE BASE FROM KNIFE RIVER		
Location Sampled:	HAUL ROAD AGGREGATE BASE AT STATION 113+50		

### Sample Data

Cc	Cu	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
		25	3.848	0.212		38.5	46.9	14.6	



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(6/10/20)





**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## GRAIN SIZE DISTRIBUTION

ASTM C136 & D422

Report To: RJ Zavoral and Sons  
1706 Bygland Rd SE  
East Grand Forks MN 56721  
Attention: Zach Bopp, PM


Project: Solid Waste Management Area Cell 1  
Project Number: 20.BIS09947.000  
Location: Bismarck Landfill  
Bismarck, ND

### Sample Information

Sample Number:	5	Date Sampled:	6/1/2020
Project Specifications:	NDDOT CLASS 13	Sampled By:	NTI
Aggregate Type:	NDDOT CLASS 13, AGGREGATE BASE FROM KNIFE RIVER		
Location Sampled:	HAUL ROAD AGGREGATE BASE AT STATION 15+00		

### Sample Data

Cc	Cu	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
		25	2.85	0.202		34.0	51.2	14.8	



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(6/12/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## GRAIN SIZE DISTRIBUTION

ASTM C136 & D422

Report To: RJ Zavoral and Sons  
1706 Bygland Rd SE  
East Grand Forks MN 56721  
Attention: Zach Bopp, PM


Project: Solid Waste Management Area Cell 1  
Project Number: 20.BIS09947.000  
Location: Bismarck Landfill  
Bismarck, ND

### Sample Information

Sample Number:	6	Date Sampled:	6/2/2020
Project Specifications:	NDDOT CLASS 13	Sampled By:	NTI
Aggregate Type:	NDDOT CLASS 13, AGGREGATE BASE FROM KNIFE RIVER		
Location Sampled:	HAUL ROAD AGGREGATE BASE AT STATION 129+00		

### Sample Data


Cc	Cu	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
		25	5.826	0.426		46.1	41.3	12.6	



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

  
Tyler Hall  
(6/12/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## LABORATORY COMPACTION CHARACTERISTICS OF SOIL

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	Zach Bopp, PM	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

### Sample Information


Sample Number:	P-1	Date Sampled:	3/31/2020
Location Sampled:	CELL #1 - SOUTH		
Soil Type:	SANDY FAT CLAY, BROWN (CH)		

### Laboratory Information

Test Method:	ASTM D1557 Method A	Rammer Type:	Manual
Preparation Method:	Dry		

### Sample Data

Maximum Dry Density:	104.6 pcf	MC% As Received:	
Optimum Water Content:	19.9 %		



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(4/6/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## LABORATORY COMPACTION CHARACTERISTICS OF SOIL

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	Zach Bopp, PM	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

### Sample Information


Sample Number:	P-1	Date Sampled:	3/31/2020
Location Sampled:	CELL #1 - SOUTH		
Soil Type:	SANDY FAT CLAY, BROWN (CH)		

### Laboratory Information

Test Method:	ASTM D1557 Method A	Rammer Type:	Manual
Preparation Method:	Dry		

### Sample Data

Maximum Dry Density:	104.6 pcf	MC% As Received:	
Optimum Water Content:	19.9 %		



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(4/6/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## LABORATORY COMPACTION CHARACTERISTICS OF SOIL

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	Zach Bopp, PM	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

### Sample Information


Sample Number:	P-2	Date Sampled:	3/31/2020
Location Sampled:	CELL #1 - MIDDLE		
Soil Type:	SANDY LEAN CLAY, (CL) LIGHT BROWN TO GRAY		

### Laboratory Information

Test Method:	ASTM D1557 Method A	Rammer Type:	Manual
Preparation Method:	Dry		

### Sample Data

Maximum Dry Density:	100.4 pcf	MC% As Received:	
Optimum Water Content:	20.9 %		



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(4/6/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## LABORATORY COMPACTION CHARACTERISTICS OF SOIL

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	Zach Bopp, PM	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

### Sample Information


Sample Number:	P-2	Date Sampled:	3/31/2020
Location Sampled:	CELL #1 - MIDDLE		
Soil Type:	SANDY LEAN CLAY, (CL) LIGHT BROWN TO GRAY		

### Laboratory Information

Test Method:	ASTM D1557 Method A	Rammer Type:	Manual
Preparation Method:	Dry		

### Sample Data

Maximum Dry Density:	100.4 pcf	MC% As Received:	
Optimum Water Content:	20.9 %		



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(4/6/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## LABORATORY COMPACTION CHARACTERISTICS OF SOIL

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	Zach Bopp, PM	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

### Sample Information


Sample Number:	P-3	Date Sampled:	4/8/2020
Location Sampled:	CELL #1 - MIDDLE #2		
Soil Type:	SANDY FAT CLAY, LIGHT BROWN TO GRAY		

### Laboratory Information

Test Method:	ASTM D1557 Method A	Rammer Type:	Manual
Preparation Method:	Dry		

### Sample Data

Maximum Dry Density:	100.7 pcf	MC% As Received:	
Optimum Water Content:	19.4 %		



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(4/21/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## LABORATORY COMPACTION CHARACTERISTICS OF SOIL

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	Zach Bopp, PM	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

### Sample Information


Sample Number:	P-4	Date Sampled:	4/8/2020
Location Sampled:	CELL #1, CENTER OF NORTH HAUL ROAD		
Soil Type:	SANDY FAT CLAY, BROWN		

### Laboratory Information

Test Method:	ASTM D1557 Method A	Rammer Type:	Manual
Preparation Method:	Dry		

### Sample Data

Maximum Dry Density:	99.5 pcf	MC% As Received:	
Optimum Water Content:	21.3 %		



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(4/21/20)





**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## LABORATORY COMPACTION CHARACTERISTICS OF SOIL

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	Zach Bopp, PM	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

### Sample Information


Sample Number:	P-5	Date Sampled:	4/15/2020
Location Sampled:	MIDDLE #3 (NORTH) OF CELL #1		
Soil Type:	SANDY FAT CLAY, LIGHT BROWN TO GRAY		

### Laboratory Information

Test Method:	ASTM D1557 Method A	Rammer Type:	Manual
Preparation Method:	Dry		

### Sample Data

Maximum Dry Density:	101.9 pcf	MC% As Received:	
Optimum Water Content:	20.2 %		



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(4/21/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## LABORATORY COMPACTION CHARACTERISTICS OF SOIL

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	Zach Bopp, PM	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

### Sample Information


Sample Number:	P-6	Date Sampled:	4/15/2020
Location Sampled:	EXISTING SAND MATERIAL ON SITE (SEE ALSO MA-1 GRADATION)		
Soil Type:	SAND, FINE GRAINED (SP), LIGHT BROWN		

### Laboratory Information

Test Method:	ASTM D1557 Method A	Rammer Type:	Manual
Preparation Method:	Wet		

### Sample Data

Maximum Dry Density:	101.7 pcf	MC% As Received:	
Optimum Water Content:	9.2 %		



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(4/30/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## LABORATORY COMPACTION CHARACTERISTICS OF SOIL

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	Zach Bopp, PM	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

### Sample Information


Sample Number:	p-7	Date Sampled:	5/18/2020
Location Sampled:	CELL #1 BOTTOM; WEST END		
Soil Type:	SANDY LEAN CLAY, GRAY		

### Laboratory Information

Test Method:	ASTM D1557 Method A	Rammer Type:	Manual
Preparation Method:	Dry		

### Sample Data

Maximum Dry Density:	112.3 pcf	MC% As Received:	19.5
Optimum Water Content:	12.7 %		



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(6/1/20)



**NTI**  
NORTHERN  
TECHNOLOGIES, LLC

**Bismarck**  
2110 Lovett Ave, Unit #5  
Bismarck, North Dakota 58504  
P: 701.425.5791 F: 701.232.1864  
[www.NTIgeo.com](http://www.NTIgeo.com)

## LABORATORY COMPACTION CHARACTERISTICS OF SOIL

Report To:	RJ Zavoral and Sons 1706 Bygland Rd SE East Grand Forks MN 56721	Project:	Solid Waste Management Area Cell 1
Attention:	Zach Bopp, PM	Project Number:	20.BIS09947.000
		Location:	Bismarck Landfill Bismarck, ND

### Sample Information


Sample Number:	P-8	Date Sampled:	5/20/2020
Location Sampled:	NDDOT CLASS 13 AGGREGATE BASE FROM SOURCE KNIFE RIVER		
Soil Type:	NDDOT CLASS 13 AGGREGATE BASE		

### Laboratory Information

Test Method:	ASTM D1557 Method B	Rammer Type:	Manual
Preparation Method:	Wet		

### Sample Data

Maximum Dry Density:	133.6 pcf	MC% As Received:	
Optimum Water Content:	7.6 %		



Comments:

Cc:

Submitted by,  
**Northern Technologies, LLC**

Tyler Hall  
(6/5/20)

## **DISCLAIMER FOR THE USE OF ELECTRONIC MEDIA**

At your request, Houston Engineering Inc. ("Houston") is transferring information to you in electronic format (the "Electronic Information") concerning the project referenced below. This transfer constitutes a non-exclusive, limited license to you to use the information in the electronic file(s). Nothing in this transfer should be construed to create any right of the user to rely on the information provided or that the use of this Electronic Information implies that it has been reviewed or approved by Houston. Any use of this information is at the sole risk and liability of the user. Because information presented in electronic format can be modified, unintentionally or otherwise, Houston reserves the right to remove all indicia of ownership and/or involvement from the Electronic Information. The following shall apply to all Electronic Information provided by Houston in connection with this project:

1. Houston makes no performance guarantees, express or implied warranties, and assumes no obligation or liability for the reliability or accuracy of the information contained therein; or for the accuracy of the information translated by Houston's software for use with the end user's software. Moreover, any reuse of electronically stored documents imports a risk of error and misinterpretation through corruption of data, incompatibilities of computer programs, intentional manipulation and the like. As files distributed electronically may be subject to data erosion, erasure and/or alteration, and computer systems and software become obsolete over time, Houston makes no representations as to long term compatibility, usability, or readability of documents resulting from use of software application packages, operating systems, or computer hardware.
2. Houston assumes no liability for hardware or software damage that may result from the use of Electronic Information provided, or by electronic transfer due to viruses that may reside on the electronic media when transferred to the user.
3. Any use of this Electronic Information is at the sole risk and liability of the user. User is solely responsible for updating the information to reflect any changes following the preparation date of the Electronic Information conveyed by Houston. User agrees to make no claim and hereby waives, to the fullest extent permitted by law, any claim or cause of action of any nature against Houston, its officers, directors, employees, agents or subconsultants that may arise out of or in connection with the use of the Electronic Information.
4. User agrees not to forward, re-transmit or otherwise provide the Electronic Information to any third party including, without limitation, any subcontractor, agent or consultant without the prior written consent of Houston. If such consent is given, you agree to the fullest extent permitted by law, to hold harmless, indemnify, and defend Houston and each of its officers, directors, employees, agents, or subconsultants from and against any and all costs, losses and damages (including, but not limited to, all reasonable fees and charges of engineers, architects, attorneys and other professionals and all court or arbitration or other dispute resolution costs) that may arise out of or in connection with such third party use of the Electronic Information.
5. If for any reason a conflict exists between the Electronic Information provided and the stamped/sealed, signed plans and specifications, the stamped/sealed and signed plans and specifications shall take precedence in resolving any conflict, error, ambiguity or discrepancy.
6. Houston makes no performance guarantees, and assumes no obligation or liability for the accuracy of the information translated for use with the end users' software.

**By downloading and/or accepting the Electronic Information, the user acknowledges and agrees to the foregoing conditions.**

Project: Bismarck Cell 1 Construction - LF 2021-001 (Solicitation Support)

Date: \_\_\_\_\_

Company: \_\_\_\_\_

Signature: \_\_\_\_\_

Its: \_\_\_\_\_

**SPECIAL PROVISION NO 35**  
**Geotextile Fabric**

**PART 1 – GENERAL**

**SUMMARY**

This section covers the work necessary to furnish and install geotextile fabric materials.

**MEASUREMENT AND PAYMENT**

Measurement: Work specified in this section will be measured based upon plan area in square yard (SY) of the proposed limits (pay limits) of the geotextile fabric as shown in the Contract Drawings, taken as a 3-dimensional projected area.

Payment: Payment for this includes, but is not limited to, the following Work:

- Furnishing and installing geotextile fabric as shown in the Contract Documents
- Preparation of surfaces in preparation for geotextile placement
- All seaming operations to join panels, if applicable.
- Protect of geotextile fabric materials during placement and backfilling operations as indicated in the Contract documents

**SUBMITTALS**

Submit Manufacturer's Certification for the geotextile fabric materials indicating that the materials meet the physical requirements stated in Part 2 of this specification section.

**DELIVERY, STORAGE, AND HANDLING**

Geotextile will be protected from precipitation, inundation, ultraviolet exposure, dirt puncture, cutting, and other damaging or deleterious condition.

**PART 2 - PRODUCTS**

**GENERAL**

CONTRACTOR will furnish materials whose "Minimum Average Roll Values", as defined by the Federal Highway Administration (FHWA), meet or exceed the criteria listed in this section.

Nonwoven geotextile products will be comprised of polymeric yarns of fibers oriented into a stable network, which retains its relative structure during handling, placement, and long-term service.

**EQUIPMENT**

CONTRACTOR will furnish all necessary equipment required to accomplish the installation of the

## **MATERIALS**

The geotextile fabric will be a nonwoven polypropylene or polyester geotextile, supplied by the Geosynthetics Contractor, which meets the requirements of **TABLE 1** below. The geotextile shall be TenCate Mirafi S1600 or approved equal.

## **GEOTEXTILE SEAMING**

Geotextile seams will be thermally seamed or sewn with polymeric thread. The thread will be capable of supplying a seam strength efficiency of 80 percent of the required tensile strength utilizing a Type 401 two-thread chain stitch with a "J" seam. Cushion geotextile seams will be thermally bonded at all overlaps.

## **PART 3 EXECUTION**

### **GENERAL INSTALLATION REQUIREMENTS**

All geotextiles will be deployed in accordance with the manufacturer's recommendations, standards, and guidelines.

Geotextile procurement, transportation, storage, handling and installation will be the responsibility of the CONTRACTOR. Any damaged or unacceptable material will be replaced at the sole expense of the CONTRACTOR. During shipment and storage, the geotextile will be protected from ultraviolet light exposure, precipitation or other inundation, mud, dirt, dust, puncture, cutting or any other damaging or deleterious conditions. To that effect, geotextile rolls will be shipped and stored in relatively opaque and watertight wrappings.

Geotextile rolls will be handled in such a way that they are not damaged.

Geotextile will be securely anchored and then deployed in such a manner as to continually keep the geotextile sheet in sufficient tension to preclude folding or wrinkling.

Geotextile will be weighted with sandbags or the equivalent to prevent movement caused by wind. Such sandbags will be installed during placement and will remain until replaced with cover material.

CONTRACTOR will take any necessary precautions to prevent damage to underlying materials during placement of the geotextile.

During placement of geotextile, care will be taken not to entrap in the geotextile, stones, excessive dirt, or moisture that could damage the geomembrane or hamper subsequent seaming.

Geotextile will not be exposed to precipitation prior to being installed. Wrappings protecting geotextile rolls will be removed less than one hour prior to unrolling the geotextile. After the wrapping has been removed, the geotextile will not be exposed to direct sunlight for more than 15 days.

CONTRACTOR will pay particular attention at seams such that no earth cover material is inadvertently inserted beneath the geotextile.

All sewing will be done using polymeric thread with properties equal to or exceeding those of the geotextile.

CONTRACTOR will place all cover materials in such a manner such that the geotextile is not damaged, minimal slippage of the geotextile or underlying layers occurs, and no excess tensile stresses are present in the geotextile.

Soil will be placed over the geotextile by “rolling” (not dragging) a minimum of 12 inches of material ahead of all construction equipment.

On slopes steeper than 6H:1V, cover material will be placed from the bottom of the slope proceeding upward.

No construction equipment with average ground pressure greater than 8 psi will operate on slopes unless they are more than 10 feet from exposed geotextiles and are operating on 2 feet or more of cover material thickness.

Operation of equipment over geotextile will be in conformance with the following guidelines:

<u>Average Equipment Ground</u> <u>Pressure (psi)</u>	<u>Minimum Lift thickness Under</u> <u>Tracks (in)</u>
5	12
5-8	24
>8	36

## **SEAMING OF GEOTEXTILE**

On slopes flatter than or equal to 10H:1V, adjacent cushion geotextile panels may be sewn, or heat bonded. All seaming, heat bonding or overlapping of sheets will be done in accordance with the manufacturer's recommendations. For overlapped seams that are thermally bonded, overlap distances will be a minimum of 6 inches.

n slopes greater than 10H:1V, adjacent panels will be sewn or heat bonded. All seams on such slopes will be oriented parallel to (in the direction of) the slope.

Sewn seams will use a Type 401 stitch. One or two rows of stitching may be used.

Seams may be heat bonded using thermal fusion or ultrasonic devices.

Adjacent panels will be overlapped a minimum of 6 inches prior to seaming.

Care will be taken not to introduce soil to the collection system drainage layer stone during backfilling operations

## **REPAIRS**

Holes or tears in the fabric will be repaired as follows: A fabric patch made from the same geotextile will be thermally welded into place. Provide a minimum overlap of 12 inches in all directions. Should any tear exceed 10 percent of the width of the roll, that roll will be removed from the slope and replaced.

Care will be taken to remove any soil or other materials that may have penetrated the torn geotextile.



Log any defects, holes, and tears that are identified and repaired.

## TESTING

Manufacturer conformance/manufacturer testing, prior to construction, of all geotextile materials is the responsibility of the CONTRACTOR. Results of the conformance/manufacturer testing are to be submitted to the ENGINEER for approval prior to delivery and acceptance of the material for use in the project. Field quality assurance activities will be performed in accordance with the Construction Quality Assurance Manual and will include visual field inspection by the ENGINEER.

## PROTECTION

Geotextiles will be stored in such a manner to protect them from puncture, dirt, grease, water, mud, or excessive heat.

TABLE 1 MINIMUM REQUIRED PROPERTIES CUSHION GEOTEXTILE (NONWOVEN POLYPROPYLENE OR POLYESTER)				
PROPERTIES AND REQUIREMENTS	QUALIFIER	UNITS	SPECIFIED VALUES <sup>(1)</sup>	TEST METHOD
Fabric Mass Per Unit Area	Minimum <sup>(1)</sup>	oz/sy	16	ASTM D 5261
Grab Tensile Strength <sup>(2)</sup>	Minimum <sup>(1)</sup>	lbf	425	ASTM D4632
Grab Tensile Elongation <sup>(2)</sup>	Minimum <sup>(1)</sup>	%	50	ASTM D 4632
CBR Puncture Strength	Minimum <sup>(1)</sup>	lbf	1200	ASTM D 6241
UV Resistance <sup>(3) (4)</sup>	Minimum <sup>(1)</sup>	%	80	ASTM D 4355
Trapezoidal Tear Strength	Minimum	lb	155	ASTM D 4533

Notes:

- (1) All values represent minimum average roll values [MARVs} (i.e., any roll in a lot should meet or exceed the values in this table).
- (2) Minimum value measured in either direction.
- (3) Ultraviolet resistance requirement is at 500 hours of exposure.
- (4) Manufacturer to provide factory certification